

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1976

DEC 96 10:27 A.M. RECEI
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER
 WAYNE COUNTY, MI EDS

For corners in

WAYNE

(County)

Located In:
 CITY OF DETROIT

Corner Code #

1. Public Land Survey

T 1S R 11E M-1
 T R COMMON CORNER
 T R TO
 T 1SR12E A-01 ✓

2. Property Controlling
 in Section

S T R

3. Miscellaneous
 Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: DEC. 6, 1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

I, MARTIN C. DUNN, in a field survey on NOVEMBER 10, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

96325381

A. Description of original monument and accessories and/or subsequent restoration:
 UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY (DATED SEPT., 1816), JOSEPH FLETCHER SET A POST.
 NO EVIDENCE OF ORIGINAL CORNER FOUND.

PLATS

L. 35 P. 47	FOX & O'CONNOR'S SUBDIVISION	APRIL 22, 1916
L. 36 P. 45	THOMSON WOOD'S SUBDIVISION	AUGUST 16, 1916
L. 7 P. 27	JOHN B. SOSNOWSKI EIGHT MILE ROAD SUBDIVISION	DECEMBER 22, 1923
L. 63 P. 68	ASSESSOR'S BASE LINE SUPERHIGHWAY SUBDIVISION	JANUARY 25, 1929

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON REROD IN EXISTING MONUMENT BOX @ INTERSECTION OF DEQUINDRE AND 8 MILE (ASPHALT).
 VERIFIED LOCATION WITH TIES TO ADJACENT SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

M-1 TO M-2 2639.95' (M.) 2640.00' (R.)
 M-1 TO B-2 2647.08' (M.) 2647.26' (R.)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 NORTHEAST CORNER SECTION 1 T.1S., R.11E. (COMMON TO ALL THREE COUNTIES)

PLACED BRASS WAYNE COUNTY REMONUMENTATION WASHER AND PLASTIC CAP #30081 ON EXISTING 1/2" IRON REBAR WITHIN AN EXISTING MONUMENT BOX.

WITNESSES

N.65°E.	61.31'	SET PK NAIL WITH TAG IN NORTHWEST FACE OF UTILITY POLE
S.36°E.	91.74'	SET PK NAIL WITH TAG IN SOUTHWEST FACE OF UTILITY POLE IN MEDIAN
S.62°W.	94.03'	FOUND FORM NAIL WITH M.S.H.D. TAG
N.79°W.	88.19'	SET PK NAIL WITH TAG IN NORTHEAST FACE OF UTILITY POLE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER

Signed by

Martin C. Dunn

Date

12-23-96

Surveyor's Michigan License No. _____

4R
 7D
 DBJ