

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located in:  
GREENFIELD TWP  
(NOW CITY OF DETROIT)

Corner Code #

1. Public Land Survey	T	<del>1S</del> R	<del>11E</del>	<del>M2</del>
	T	<u>1S</u> R	<u>12E</u>	<u>ALSO</u>
	T	R		<u>COMMON</u>
	T	R		<u>TO A-2</u>
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *ncd.*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1						
3												
4	7	8	8	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEVEN E. DUNN, in a field survey of: OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 34 P. 28  
L. 34 P. 47  
L. 36 P. 45  
L. 48 P. 65

CADILLAC HEIGHTS NO. 3  
BURTON'S 7 MILE SUBDIVISION  
THOMSON WOOD SUBDIVISION  
JOHN B. SOSNOWSKI CONANT AVE. SUBDIVISION

MARCH 22, 1916  
APRIL 7, 1916  
AUGUST 9, 1916  
MARCH 19, 1916



95263078

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 T.1S, R.11E. COMMON TO A-2 T.1S, R.12E.

NO EVIDENCE OF CORNER FOUND.

HELD FOUND MONUMENTS ON OUTER DRIVE TO ESTABLISH EAST/WEST LINE. HELD IRON PIPES ON DEQUINDRE TO ESTABLISH NORTH/SOUTH LINE. VERIFIED LOCATION BY USING OTHER FOUND IRONS AND MONUMENTS ALONG WITH DISTANCES TO ADJOINING SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

M-2 TO M-3 2618.35' (M.) 2619.13' (R.)  
M-2 TO M-1 2639.95' (M.) 2640.00' (R.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

95 DEC - 8 PM 2:14

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ. 222°	33.30'	SET PK AND W.C.R. TAG IN CURB
AZ. 162°	69.07'	SET PK AND W.C.R. TAG IN SOUTHWEST FACE OF UTILITY POLE
AZ. 21°	82.64'	SET PK AND W.C.R. TAG IN SOUTHEAST FACE OF UTILITY POLE
AZ. 326°	55.43'	SET PK AND W.C.R. TAG IN SOUTHWEST FACE OF UTILITY POLE

*ncd.*

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn Date DECEMBER 5, 1995  
Surveyor's Michigan License No. 28408