

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In: GREENFIELD TWP
(NOW CITY OF DETROIT)

Corner Code #

1. Public Land Survey

T ~~18~~ R 11E

~~M-3~~

T 18 R 12E

ALSO

~~T~~ R

COMMON

T R

TO A-3

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Compliance with
ACT 945, P.A. 1990

APPROVED ON: DEC 5 1995 *ncd.*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 33 P. 81	CADILLAC HEIGHT	JANUARY 24, 1916
L. 34 P. 10	CADILLAC HEIGHTS NO.2	MARCH 7, 1916
L. 34 P. 28	CADILLAC HEIGHTS NO. 3	MARCH 22, 1916
L. 34 P. 47	BURTON'S 7 MILE SUBDIVISION	APRIL 7, 1916

95 DEC -8 PM 2: 11
 FOREST E. YOUNGBLOOD
 REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 T.1S, R.11E. COMMON TO A-3 T.1S, R.12E.

NO EVIDENCE OF CORNER FOUND;

SET CORNER USING CURB SPLITS.
VERIFIED LOCATION USING ADJACENT SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

M-3 TO M-4 2644.83' (M.) 2644.90' (R.)
M-3 TO M-2 2618.35' (M.) 2619.13' (R.)
M-3 TO L-3 2632.58' (M.) 2632.28' (R.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.



95263079

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ. 32°	47.89'	DETROIT CONTROL MONUMENT
AZ. 132°	37.39'	PK NAIL IN CONC. WALK W/W.C.R. TAG
AZ. 207°	42.56'	PK NAIL W/W.C.R. TAG IN NORTHWEST FACE OF UTILITY POLE
AZ. 318°	39.67'	PK NAIL W/W.C.R. TAG IN NORTHEAST FACE OF UTILITY POLE

H
 7 D
 712.

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408