

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

WAYNE

(County)

Located In: GREENFIELD TWP  
(NOW CITY OF DETROIT)

Corner Code #

Public Land Survey

T ~~18~~ R ~~11E~~  
T 15 R 12E  
T R  
T R  
S T R  
S T R  
S T R  
S T R

M-4  
ALSO  
COMMON  
TO A-4 ✓

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
2. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6												
7												
8	18	17	16	15	14	13						
9												
10	18	20	21	22	23	24						
11												
12	30	29	28	27	26	25						
13												
	31	32	33	34	35	36						

STEVEN E. DUNN, in a field survey on OCTOBER 15, 19 95, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore is required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 29 P. 79	OAKDALE SUBDIVISION	NOVEMBER 6, 1913
L. 33 P. 81	CADILLAC HEIGHTS	JANUARY 24, 1916
L. 34 P. 10	CADILLAC HEIGHTS NO. 2	MARCH 7, 1916
L. 35 P. 14	LELAND HEIGHTS SUBDIVISION	MAY 9, 1916



95263080

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 T.1S, R.11E. COMMON TO A-4 T.1S, R.12E.

NO EVIDENCE OF CORNER FOUND.

RE-ESTABLISHED CORNER USING FOUND IRONS ALONG 17' ALLEY AND IRONS ALONG DEQUINDRE ROAD. VERIFIED LOCATION USING BACK OF CURB SPLITS AND DISTANCES TO ADJACENT SECTION CORNERS.

FIELD MEASUREMENTS AND RECORDED DISTANCES

M-4 TO M-3 2644.83' (M.) 2644.90' (R.)  
M-4 TO M-5 2635.36' (M.) 2637.65' (R.)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

FOREST E. YOUNGBLOOD  
REGISTERED DEEDS  
MICHIGAN STATE BOARD OF LAND SURVEYORS

95 DEC -8 PM 2:11

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 T.1S, R.11E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #28408 ON 1/2" x 18" IRON IN A MONUMENT BOX.

WITNESSES

AZ. 35°	47.11'	DETROIT CONTROL MONUMENT IN WALK
AZ. 130°	38.33'	SET PK NAIL WITH WITNESS TAG IN EAST FACE OF WALK @ BUS STOP
AZ. 200°	48.72'	SET PK NAIL WITH WITNESS TAG IN CONC. CURB
AZ. 285°	57.07'	FOUND PK NAIL IN SOUTH FACE OF UTILITY POLE

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION AS INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408

4  
7 D  
M.A.