

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

FEB 28 2000

SECTION

For corners in

<u>WAYNE</u> (County)	Located In: CITY OF DETROIT	Corner Code # B-1
1. Public Land Survey	T <u>1S.</u> R <u>12E.</u>	<u>B-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Liber-30836 Page-21
 99590798 12/23/1999
 F.E. Youngblood, Wayne Co. Register of Deeds
 RDANDSYL

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-10-99
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, STEPHEN R. JACOBI, in a field survey in, DECEMBER 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1817

PLATS:	L.35, P.47	FOX O'CONNORS SUBDIVISION	JUNE 01, 1916
	L.62, P.95	CLAIRMONT PARK SUBDIVISION NO. 1	APRIL 11, 1928
	L.72, P.10	ROSE-ROSSIN SUBDIVISION	
MAP NO. 91	WAYNE COUNTY CARTOGRAPHIC MAP		AUGUST 18, 1952

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-1), NORTH 1/4 CORNER, SECTION 6, T. 1 S., R. 12 E., WAYNE COUNTY CORNER IS NOT COMMON TO B-13, T. 1 N., R. 12 E., MACOMB COUNTY

RE-ESTABLISHED CORNER USING FOUND IRONS AND MONUMENTS WITH REFERENCE TO SAID "CLAIRMONT PARK SUB'N No.1"

VERIFIED LOCATION USING WALK AND CURB SPLITS OF ADJACENT BLOCKS.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

- B-1 TO B-13 (MACOMB COUNTY) - 1.14'
- B-1 TO C-1 2620.79'
- ANGLE B-13/B-1/C-1 180°00'00"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-1), NORTH 1/4 CORNER, SECTION 6, T. 1 S., R. 12 E., WAYNE COUNTY, CORNER IS NOT COMMON TO B-13, T. 1 N., R. 12 E., MACOMB COUNTY SET WAYNE COUNTY REMONUMENTATION CAP ON 1/2" X 18" IRON ROD IN ASPHALT PAVEMENT

WITNESSES

S.35°E. 54.17'	FOUND "+" SCRIBED ON TOP OF THE SOUTH BOLT OF LIGHT POLE BASE.
N45°W. 48.23'	FOUND PK NAIL AND WASHER STAMPED #14684 IN SW FACE OF UTILITY POLE..
S.05°W. 55.10'	FOUND PK NAIL AND WASHER STAMPED #14684 IN EAST FACE OF UTILITY POLE.
S.28°E. 53.60'	SET MAG NAIL AND MACOMB COUNTY WITNESS TAG IN NE FACE OF 10" TREE.
WEST 1.14'	FOUND MACOMB COUNTY REMON CAP IN MONUMENT BOX.

THE SELECTED LOCATION IS CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Stephen R. Jacobi Date 12-21-99
 Surveyor's Michigan License No. 43057

R LCR 9 4R 1Pa A DPZ