

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 28452 PAGE 768

For corners in **COMMISSION**

WAYNE

(County)

Located In: **HAMTRAMCK TWP  
(NOW CITY OF DETROIT)**

Corner Code #

- |                                    |   |    |   |     |     |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey              | T | 1S | R | 12E | E-2 |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
| 2. Property Controlling in Section | S |    | T | R   |     |
|                                    | S |    | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |    | T | R   |     |
|                                    | S |    | T | R   |     |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: **DEC 5 1995** *YCA*

WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, MARTIN C. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	6	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	18	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

**PLATS**

L. 37 P. 11  
L. 55 P. 24

THOMAS BROTHER'S OAKLEY HEIGHTS SUBDIVISION  
MOUND BOULEVARD SUBDIVISION

NOVEMBER 2, 1916  
JUNE 12, 1925



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

NO EVIDENCE OF CORNER FOUND.  
HELD FOUND MONUMENTS ON SOUTH LINE OF OUTER DRIVE. OFFSET AND EXTENDED LINE RECORD DISTANCES.  
VERIFIED LOCATION WITH OTHER FOUND MONUMENTS AND IRONS.

**FIELD MEASUREMENTS AND RECORDED DISTANCES**

E-2 TO E-1 2639.43' (M.) 2640.67' (R.) 2640.00' (GLO)  
E-2 TO E-3 2642.22' (M.) 2643.06' (R.) 2640.00' (GLO)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-2 T.1S., R.12E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" ROD IN MONUMENT BOX.

**WITNESSES**

- |          |        |   |
|----------|--------|---|
| AZ. 200° | 82.90' | FOUND NAIL WITH STATE OF MICHIGAN TAG IN NORTHWEST FACE OF UTILITY POLE |
| AZ. 90°  | 50.41' | FOUND NAIL WITH STATE OF MICHIGAN TAG IN SOUTH FACE OF TRAFFIC POLE     |
| AZ. 340° | 79.42' | FOUND NAIL WITH STATE OF MICHIGAN TAG IN NORTHEAST FACE OF UTILITY POLE |
| AZ. 270° | 41.20' | SET PK NAIL AND W.C.R. TAG IN TOP OF CURB                               |

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Martin C. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 30081

95263083

95 DEC -8 PM 2:11

FOREST E. YOUNGBLOOD  
REGISTERED PROFESSIONAL SURVEYOR

4  
70  
YCA