

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

WAYNE

(County)

Located In: HAMTRAMCK TWP (NOW CITY OF DETROIT) Corner Code #

Table with 3 columns: Description (1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec.), T, S, R, and Corner Code # (E-3).

Compliance with ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 3.

I, MARTIN C. DUNN, in a field survey on OCTOBER 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

Table listing plats (L. 36 P. 24, L. 38 P. 63, L. 40 P. 96, L. 41 P. 82, L. 51 P. 99) and subdivisions (KERN HEIGHTS LOUIS N. HILSENDEGEN'S SUBDIVISION, NORTH DETROIT HOMES SUBDIVISION NO. 2, HILLKERN SUBDIVISION, MOUND SUBDIVISION, ST. LOUIS PARK SUBDIVISION) with dates (JULY 21, 1916; JUNE 4, 1917; DECEMBER 2, 1919; APRIL 22, 1920; DECEMBER 11, 1924).



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND.

HELD FOUND IRON PIPE AT NORTHEAST CORNER OF MOUND AND 7 MILE AND HELD FOUND IRON ON NORTH LINE OF 7 MILE. HELD MONUMENT ON SOUTHEAST CORNER OF MOUND AND EMERY WITH IRON PIPE AT NORTHEAST CORNER OF MOUND AND 7 MILE. OFFSET LINES RECORD DISTANCES AND INTERSECTED LINES TO ESTABLISH CORNER.

VERIFIED LOCATION EAST AND WEST USING DISTANCE TIES TO FOUND IRONS ALONG SOUTH LINE OF 7 MILE. VERIFIED LOCATION NORTH AND SOUTH USING CURB SPLITS ALONG 7 MILE.

FIELD MEASUREMENTS AND RECORDED DISTANCE

E-3 TO E-2 2642.22' (M.) 2643.06' (R.) 2640.00' (GLO)
E-3 TO E-4 2652.91' (M.) 2651.83' (R.) 2640.00' (GLO)

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 T.1S., R.12E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

Table with 4 columns: Azimuth (AZ), Distance, and Description (SET PK NAIL WITH W.C.R. TAG IN EAST SIDE OF TRAFFIC POLE, SET PK NAIL WITH W.C.R. IN SOUTHEAST SIDE OF TRAFFIC POLE, SET PK NAIL WITH W.C.R. TAG IN NORTHEAST SIDE OF UTILITY POLE, SET PK NAIL WITH W.C.R. TAG IN SOUTH SIDE OF UTILITY POLE).

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Martin C. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 30081

Vertical stamp: FOREST E. YOUNGBLOOD, REGISTERED PROFESSIONAL SURVEYOR, 95 DEC - 8 PM 2: 11, 95263084, H 7 D, WCD.