

FILE DO NOT MAIL

DEC 22 1998

For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY 8  
REMONUMENTATION

MAR 16 1999

Liber 30032

Page 21.0

984530315

12/22/1998

981734M

WAYNE  
(County)

Located In: CITY OF DETROIT  
Corner Code #

SECTION

- 1. Public Land Survey T 1 S. R 12 E. E-1  
T R  
T R  
✓ T 18 R 12 E TO  
S T R E-13  
S T R T IN R I Z E  
S T R  
S T R
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-9-98  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

I, STEPHEN R. JACOBI, in a field survey on, NOVEMBER 27, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1817

PLATS:

L. 36, P. 68 "NORTH HAMTRAMCK SUB." 9-11-1916  
L. 41, P. 93 "BELL REALTY CO'S LOG CABIN PARK"  
L. 63, P. 5 "ASSESSORS BASE LINE SUPERHIGHWAY SUBDIVISION" 5-24-1928

LCRC:

L. 3612, P. 451 MON BOX, NO IRON INSIDE JAMES H BUCKERFIELD, PS #10868 3-26-84  
L. 3858, P. 732-3 IRON IN MON BOX GEORGE E. DELY, PS #5234 7-10-84

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-1), NORTHEAST CORNER, SECTION 5, T. 1 S., R. 12 E., WAYNE COUNTY CORNER IS COMMON TO E-13, T.1 N., R. 12 E., MACOMB COUNTY

FOUND 3/8" BAR IN MONUMENT BOX WITH NO LID.

VERIFIED LOCATION USING FOUND PROPERTY CORNERS WITH REFERENCE TO THE ABOVE LISTED PLATS AND METCO SERVICES ALTA, JOB 96-153, DATED 10/1996

FOUND WITNESSES:

N.W.	68.61' (68.55'M)	FOUND PK NAIL WITH WITNESS TAG IN SW FACE OF UTILITY POLE.	(L. 3612, P. 451)
N.E.	53.78' (53.03'M)	FOUND PK NAIL WITH WITNESS TAG IN NW FACE OF UTILITY POLE.	(L. 3612, P. 451)
S.E.	77.00' (77.14'M)	FOUND PK NAIL WITH MACOMB COUNTY WITNESS TAG SE FACE OF UTILITY POLE.	(L. 3612, P. 451)
N.E.	53.81' (53.03'M)	FOUND PK NAIL WITH WITNESS TAG IN NW FACE OF UTILITY POLE.	(L. 3858, P. 732-3)
S.E.	77.06' (77.14'M)	FOUND PK NAIL WITH MACOMB COUNTY WITNESS TAG SE FACE OF UTILITY POLE	(L. 3858, P. 732-3)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-1), NORTHEAST CORNER, SECTION 5, T. 1 S., R. 12 E., WAYNE COUNTY, INTERSECTION (ASPHALT) OF MOUND AND 8 MILE ROAD SET ALUMINUM CAP ON 1/2" IRON ROD STAMPED "WAYNE COUNTY REMONUMENTATION #43057" IN MONUMENT BOX.

WITNESSES

N.51°W.	68.55'	FOUND PK NAIL WITH WITNESS TAG IN SW FACE OF UTILITY POLE.
N.47°E.	53.03'	FOUND PK NAIL WITH WITNESS TAG IN NW FACE OF UTILITY POLE.
S.47°E.	77.14'	FOUND PK NAIL WITH MACOMB COUNTY WITNESS TAG SE FACE OF UTILITY POLE.
S.50°W.	66.30'	NE CORNER OF SQUARE CATCH BASIN CASTING.

RECORDED  
FOREST E. YOUNGLOD, REGISTERED SURVEYOR  
WAYNE COUNTY, MI  
Receipt # 101003

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Stephen R. Jacobi Date 12-16-98

Surveyor's Michigan License No. 43057

R LCR 7 4R 1PG U DBJ