

FEB 28 2000

FILE DO NOT MAIL LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE
(County)

Located In:
CITY OF DETROIT

Corner Code #

Liber-30836 Page-24
99590815 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-99
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 1S. R 12E. F-1
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, STEPHEN R. JACOBI, in a field survey in, DECEMBER 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1817

PLATS: L. 46, P. 44 "COMMISKEY'S OUTER BLVD. SUBDIVISION" NOT KNOWN

L.C.R.C.: L. 3612 P. 450 MON BOX, NO IRON INSIDE JAMES H BUCKERFIELD, PS #10868 3-26-84

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-1), NORTH 1/4 CORNER, SECTION 5, T. 1 S., R. 12 E., WAYNE COUNTY CORNER IS NOT COMMON TO F-13, T.1 N., R. 12 E., MACOMB COUNTY

ESTABLISHED NORTH-SOUTH 1/4 LINE USING FOUND BLOCK CORNERS. EXTENDED NORTH-SOUTH 1/4 LINE RECORD DISTANCE TO ESTABLISH NORTH 1/4 CORNER. CORNER FALLS ON THE SOUTH LINE OF SECTION 33, 1.11' EAST OF THE SOUTH 1/4 CORNER, T.1 N., R. 12 E., MACOMB COUNTY.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

- F-1 to G-1 2640.58'
- F-1 to F-13 (MACOMB COUNTY) 1.05'
- Angle F-13/F-1/G-1 180°00'00"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-1), NORTH 1/4 CORNER, SECTION 6, T. 1 S., R. 12 E., WAYNE COUNTY, CORNER IS NOT COMMON TO F-13, T.1 N., R. 12 E., MACOMB COUNTY SET WAYNE COUNTY REMON CAP ON 1/2" X 18" IRON REROD IN ASPHALT PAVEMENT.

WITNESSES

- N.69°E. 76.92' FOUND PK AND TAG IN SOUTH FACE OF UTILITY POLE.
- S.33°E. 74.47' FOUND MAG NAIL AND MACOMB COUNTY WITNESS TAG IN WEST FACE OF UTILITY POLE.
- S.23°W. 60.55' FOUND PK AND TAG IN EAST FACE OF UTILITY POLE.
- N.74°W. 89.80' FOUND PK AND TAG IN NORTHEAST FACE OF UTILITY POLE.
- WEST 1.05' FOUND MACOMB COUNTY REMON CAP IN MONUMENT BOX

THE SELECTED LOCATION IS CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Stephen R. Jacobi Date 12-21-99
Surveyor's Michigan License No. 43057

R LCR 9 4R 1Pa A DP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

