

For corners in

WAYNE

(County)

Located In:
CITY OF DETROIT

Corner Code #

- | | | |
|------------------------------------|--|------------|
| 1. Public Land Survey | T <u>1S</u> R <u>12E</u> | <u>G-3</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

LIBER 29356 PAGE 108

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC. 6, 1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARTIN C. DUNN, in a field survey on SEPTEMBER 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4		3	2	1					
3													
4		7	8	9		10	11	12					
5													
6		18	17	16		15	14	13					
7													
8		19	20	21		22	23	24					
9													
10		30	29	28		27	26	25					
11													
12		31	32	33		34	35	36					
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY (DATED SEPT., 1816), JOSEPH FLETCHER SET A POST. NO EVIDENCE OF ORIGINAL CORNER FOUND.

PLATS

- | | | |
|-------------|--|-----------|
| L. 34 P. 48 | STOTTERS SUBDIVISION | 4-1916 |
| L. 35 P. 76 | JAMES H. CULLEN'S SUBDIVISION | 7-20-1916 |
| L. 38 P. 5 | MORAN & HUTTOONS VAN DYKE AVE. SUBDIVISION | 3-21-1917 |
| L. 49 P. 26 | HOUSE VAN DYKE SEVEN MILE ROAD SUBDIVISION | 5-12-1924 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RE-ESTABLISHED CORNER AT THE CENTERLINES OF VAN DYKE AND 7 MILE (ASPHALT) USING FOUND IRONS AND BUILDING CORNERS. VERIFIED LOCATION BY MEASUREING UP THE ADJACENT BLOCKS USING WALK AND STREET SPLITS WITH REFERENCE TO THE ABOVE LISTED PLATS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 SOUTHWEST CORNER SECTION 3 T.1S., R.12E.

PLACED BRASS WAYNE COUNTY REMONUMENTATION WASHER AND PLASTIC CAP #30081 ON 1/2" x 18" IRON REBAR WITHIN A NEW MONUMENT BOX.

WITNESSES

- | | |
|----------------|--|
| N.65°E. 58.01' | SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN APHALT WALK. |
| S.60°E. 64.31' | SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN NORTH FACE OF CONCRETE PEDESTAL FOR SIGN. |
| S.45°W. 80.56' | SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN TOP OF CONCRETE BASE FOR LIGHT POLE. |
| N.51°W. 56.34' | SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN SOUTH FACE OF UTILITY POLE. |

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by Martin C. Dunn

Date 12-23-96

Surveyor's Michigan License No. 30081

4R
7D
D&J