

\$ 4.00 REMONUMENTATION  
\$ 7.00 DEED  
23 DEC 96 10:27 A.M. RECEI  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER EDS  
WAYNE COUNTY, MI

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located In: <u>HAMTRAMCK</u>	Corner Code # <u>G-9</u>
1. Public Land Survey	T <u>1S</u> R <u>12E</u>	<u>G-9</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**LIBER 29356 PAGE 109**  
Compliance with  
ACT 345, P.A. 1990 *DBJ*  
APPROVED ON: DEC. 6, 1996  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

I, MARTIN C. DUNN, in a field survey on NOVEMBER 9, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY (DATED SEPT., 1816), JOSEPH FLETCHER SET A POST.  
NO EVIDENCE OF ORIGINAL CORNER FOUND.

<u>PLATS</u>		
L. 16 P. 21	FRANK C. IRVINES SUBDIVISION	9-30-1891
L. 26 P. 41	PRESSLER'S SUBDIVISION	3-26-1909
L. 29 P. 86	GABLE AND PISCOPIK'S SUBDIVISION	11-17-1913
L. 31 P. 64	HARPER-VAN DYKE SUBDIVISION	12-31-1914
L. 37 P. 85	HAFEL'S SUBDIVISION	2-20-1917

D. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
RE-ESTABLISHED CORNER AT THE CENTERLINES OF VAN DYKE AND MILLER (ASPHALT) USING BUILDING LINES, STONE CURBS, AND WALK SPLITS. THE CENTERLINE OF BALDWIN WAS ESTABLISHED USING STONE CURBS AND WALK SPLITS. THE SECTION LINE WAS THEN PUT IN AT RECORD DISTANCE FROM THE CENTERLINE OF BALDWIN.  
THE LOCATION WAS VERIFIED WITH TIES TO THE BUILDINGS AND CONCRETE SLABS ALONG THE ALLEY AND ROADWAYS WITH REFERENCE TO THE ABOVE LISTED PLATS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-9 SOUTHWEST CORNER SECTION 3 T.1S., R.12E.  
PLACED BRASS WAYNE COUNTY REMONUMENTATION WASHER AND PLASTIC CAP #30081 ON 1/2" x 18" IRON REBAR WITHIN A NEW MONUMENT BOX.

<u>WITNESSES</u>		
N.70°E.	51.18'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN TOP OF CONCRETE CURB.
S.54°E.	71.75'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN CONCRETE WALK.
S.44°W.	35.49'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN TOP OF CONCRETE CURB.
N.50°W.	39.85'	SET P.K. NAIL WITH WAYNE COUNTY REMON TAG IN CONCRETE WALK.

THE SELECTED LOCATION FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Martin C. Dunn Date 12-23-96  
Surveyor's Michigan License No. 30081

4R  
7D  
*DBJ*