

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:
HAMTRAMCK TWP.
(NOW CITY OF DETROIT)

Corner Code #

1. Public Land Survey

T 1S R 12E

I-5

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *TCR*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on OCTOBER 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 46 P. 83
L. 47 P. 28
L. 55 P. 42

- TEPPERT'S PARK VIEW SUBDIVISION
LASALLE COLLEGE PARK SUBDIVISION
JEREMIAH TROMBLEY'S GRATIOT LAWN SUB.

SEPTEMBER 13, 1923
OCTOBER 19, 1923
JUNE 20, 1925



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND.

RE-ESTABLISHED CORNER BY FOUND IRONS AND BACK OF CURB SPLITS WITH REFERENCE TO THE ABOVE LISTED PLATS.

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 T.1S., R.12. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

- AZ. 55° 66.99' SET PK IN WITH TAG IN NORTH FACE OF UTILITY POLE
- AZ. 120° 49.30' SET PK NAIL WITH TAG IN NORTHEAST FACE OF UTILITY POLE
- AZ. 300° 63.02' SET PK WITH TAG IN SOUTH FACE OF UTILITY POLE
- AZ. 310° 62.40' DETROIT MONUMENT BOX

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Steven E. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 28408

95263086
95 DEC -8 PM 2:11
FORESTER, YOUNGBLOND
REGISTERED OF DEEDS

4
7D
TCR