

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION
 WAYNE
 (County)

Located In:
 CITY OF DETROIT

Corner Code #

Liber-29744 Page-1027.0
 97335334LS 12/22/1997 10:12AM

1. Public Land Survey T 1S R 12E K-4
 T R
 T R
 T R
2. Property Controlling S T R
 in Section S T R
3. Miscellaneous S T R
 Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Compliance with
 ACT 345, P.A. 1990
APPROVED ON: 12-2-97
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

I, MARTIN C. DUNN, in a field survey on NOVEMBER 24, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

UNDER CONTRACT FOR THE GLO ORIGINAL SURVEY SEPTEMBER 1816 JOSEPH FLETCHER SET A POST

PLATS		
L. 40 P. 93	"TROMBLEY PARK SUBDIVISION"	11-25-1919
L. 41 P. 67	MICHAEL GREINER ESTATE SUBDIVISION"	4-20-1920
L. 45 P. 39	"GROTTO PARK SUBDIVISION"	8-21-1924

\$7.00 DEED
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF
 WAYNE COUNTY, MI
 Receipt #43579
 \$4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RE-ESTABLISHED CORNER USING FOUND MONUMENTS ON THE WEST LINE OF SCHOENHERR, NORTH OF GREINER. HELD RECORD DISTANCE TO ESTABLISH CORNER. VERIFIED LOCATION WITH OTHER FOUND MONUMENTS AND IRONS ALONG SCHOENHERR AND GREINER.

FIELD MEASUREMENTS AND RECORDED DISTANCES

K-4 TO K-5	2641.55 (M)	40 CH. (GLO)
K-4 TO K-3	2639.69 (R&M)	40 CH. (GLO)
K-3 /K-4/K-5	180°29'21" (M)	



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 EAST QUARTER CORNER OF SECTION 11, T.1S., R.12E., WAYNE COUNTY
 PLACED ALUMINUM WAYNE COUNTY REMONUMENTATION CAP WITH #30081 ON 1/2"x18" REBAR IN NEW MONUMENT BOX

WITNESSES

43°AZ.	46.15'	SET PK NAIL W/ WAYNE COUNTY REMONUMENTATION TAG IN NORTHWEST FACE OF UTILITY POLE.
132°AZ.	38.19'	SET PK NAIL W/ WAYNE COUNTY REMONUMENTATION TAG IN SOUTHWEST FACE OF UTILITY POLE.
215°AZ.	39.85'	SET PK NAIL W/ WAYNE COUNTY REMONUMENTATION TAG IN WEST FACE OF UTILITY POLE.
302°AZ.	39.26'	SET PK NAIL W/ WAYNE COUNTY REMONUMENTATION TAG IN NORTH FACE OF UTILITY POLE.

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Martin C. Dunn Date 12/5/97
 Surveyor's Michigan License No. 30081