

RE-RECORD

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 28452 PAGE 770
LIBER 28640 PAGE 013

For corners in

WAYNE

(County)

Located In: HAMTRAMCK TWP Corner Code #
(NOW CITY OF DETROIT)

- 1. Public Land Survey T 1S R -41E 12E G-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Seg. #2

RECEIVED
5 MAR 96 10:24 A.M. RECEIPT# 188

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

\$ 4.00 REMONUMENTATION
Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995 *ACD*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Note: This Certificate is being re-recorded to correct a typographical error in the range number

I, MARTIN C. DUNN, in a field survey on OCTOBER 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8	9	10		11		12				
5													
6		18	17	16	15	14	13						
7													
8		18	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY JOSEPH FLETCHER UNDER CONTRACT DATED SEPT., 1816

PLATS

L. 22 P. 39	J.W. NUERENBERG'S SUBDIVISION	JULY 18, 1901
L. 27 P. 43	TUMEY'S SUBDIVISION	APRIL 25, 1911



95263085

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND.
HELD FOUND IRON PIPES ON WEST SIDE OF VAN DYKE. EXTENDED LINE RECORD DISTANCE TO ESTABLISHED CORNER.
VERIFIED LOCATION USING CURB SPLITS.

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

95 DEC -8 PM 2:11
FOREST E. YOUNGBLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 T.1S., R.12E. WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

- AZ. 33° 71.25' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK 0.50' SOUTHWEST OF FACE OF SIGNAL POLE
- AZ. 131° 57.02' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK 2.00' EAST OF CENTERLINE OF HYDRANT
- AZ. 233° 60.67' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK 3.20' SOUTHEAST OF FACE OF SIGNAL POLE
- AZ. 310° 62.10' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK EXPANSION JOINT

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by Martin C. Dunn

Date DECEMBER 5, 1995

Surveyor's Michigan License No. 30081

4
7D
7CD

RE-RECORD