

FEB 26 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

<u>Wayne</u> (County)	Located In: City of Detroit	Corner Code # A-1
1. Public Land Survey	T <u>1</u> S R <u>13</u> E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-18-93 *DBL*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Steven E. Dunn, in a field survey on November 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO Post - No evidence of original corner found.
GLO Original survey performed by Joseph Fletcher under contract dated 3 Sep., 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found iron rod in monument box. Verified location with centerline of Hayes Road to South and splitting back of walks.
Placed Wayne County Remonumentation marker on Iron rod in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1, T.1S.,R.13E.
Wayne County Remonumentaion marker on Iron rod in monument box.

Witnesses

- N.42°W - 60.13' Found nail and tag in NE face of utility pole.
- N.54°E. - 71.22' Set P.K. nail and W.C.R. witness tag in West face of 4" tree.
- S.46°W. - 72.90' Set P.K. nail and W.C.R. witness tag in South face of utility pole.
- S.44°E. - 73.32' Found nail and M.S.H.D. reference tag in utility pole.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn Date Nov. 30, 1993
Surveyor's Michigan License No. 28408

