

SURVEY & REMONUMENTATION

FEB 28 1994

COMMISSION

RC 1301

LI27033 PA 893

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE (County)

Table with columns: Located In: TWP. OF CANTON, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

E. PATRICK O'ROURKE in a field survey on DECEMBER 7, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numerical values for survey points.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1818) SET POST
WITNESSES: ELM 22" SOUTH 30 (19.80') (GONE)
DO 60" N30E 6 (3.96') (GONE)
WPA (1930's) FOUND MON. IN BOX (#143) MONUMENT IS APPROX. 1'-1.5' BELOW ROAD
WITNESSES: N 32.81' IRON (MEAS. 33.00') S 33.18' IRON (MEAS. 33.19')
NE 53.95' NAIL IN SOUTH SIDE TEL. POLE (GONE) SW 89.28' NAIL IN NW SIDE POWER POLE (GONE)
SE 49.85' NAIL IN NORTH SIDE 20" ELM (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO B-11 MEASURED AS 2584.98'; RECORDED WPA (1930) DISTANCES AS 2585.09' AND 2584.93'
L.17986 P.302 MONUMENT IN BOX (1972)
S'LY 32.48' NAIL AND CAP EAST SIDE UTILITY POLE (GONE)
SW 89.15' NAIL SOUTHEAST SIDE UTILITY POLE (GONE)
N'LY 33.05' LARGE IRON (MEAS. 33.00')
L.17986 P.315 MONUMENT IN BOX (1972)
WAYNE COUNTY ROAD COMMISSION WITNESSES FOUND
N'LY. 32.94' IRON (MEAS. 33.05')
SW 89.28' NAIL IN UTILITY POLE (MEAS. 89.15') (GONE)
S'LY 32.48' NAIL AND CAP EAST SIDE UTILITY POLE (GONE)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 SECTION CORNER 30, 31 T2S R8E
FOUND CONCRETE MONUMENT IN HANDHOLE ROAD BOX IN GEDDES ROAD AT COUNTY LINE AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: S 84°03'E 29.72' NAIL AND CAP EAST SIDE UTILITY POLE
N 03°48'E 31.83' WAYNE COUNTY ROAD COMMISSION NAIL AND CAP EAST SIDE UTILITY POLE
N 73°47'E 107.00' WAYNE COUNTY ROAD COMMISSION NAIL AND CAP SOUTH SIDE UTILITY POLE
S 15°11'E 105.06' NAIL AND CAP NORTH SIDE UTILITY POLE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND MONUMENT A-11

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

Handwritten numbers: 21, 116, 7