

FEB 28 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 27033 PA 894

For corners in
WAYNE

(County)

Located In:
TWP. OF CANTON

Corner Code #

1. Public Land Survey	T	2S	R	8E	B-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1302

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1800's) SET POST

WITNESSES: ASH 8 S64E 22 (14.52') (GONE)

ASH 14 N60W 19 (12.54') (GONE)

WPA (1930's)

WITNESSES: NE 57.35' NAIL IN WEST SIDE TELEPHONE POLE (GONE)

SE 38.87' NAIL IN SOUTHWEST SIDE TELEPHONE POLE (GONE)

SW 109.94' NAIL IN WEST SIDE 8" TWIN OAKS (RESET MEAS. 109.07')

SW 38.95' NAIL IN NORTHWEST SIDE WOOD SIGN POST (GONE)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO A-11 MEASURED AS 2584.98'; RECORDED WPA (1930) DISTANCES AS 2584.93' AND 2585.09';

DISTANCE TO C-11 MEASURED AS 2676.94'; RECORDED WPA (1930) DISTANCES AS 2677.81' AND 2676.85'

L.17986 P.301 FOUND MONUMENT IN BOX AT CENTERLINE GEDDES AND BARR ROADS

NE 56.80' NAIL SOUTHEAST SIDE ED POLE (FOUND BENT MEAS. 56.84')

SE 39.38' NAIL NORTHEAST SIDE ED POLE (GONE)

SW 114.1' NAIL IN SOUTHEAST SIDE 12" BUSHY TREE (GONE)

L.17986 P.313 MONUMENT IN BOX, IN CENTERLINE GEDDES PAVEMENT AND APPARENT CENTERLINE OF BARR ROAD SOUTH, FOUND

SE 39.38' NAIL IN NORTHEAST SIDE UTILITY POLE (MAY BE OLD WAYNE COUNTY ROAD COMMISSION WITNESS) (GONE)

NE 56.80' NAIL AND CAP SOUTHEAST SIDE UTILITY POLE (MAY BE OLD WAYNE COUNTY ROAD COMMISSION WITNESS) (BENT, MEAS. 56.84')

SW'LY 114.1' NAIL IN SOUTHEAST SIDE 12" APPLY TREE (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 SOUTH 1/4 CORNER 30, NORTH 1/4 CORNER 31, T2S R8E

FOUND 1/2" REROD IN CONCRETE SLIGHTLY RECESSED IN ROAD BOX (GOOD CONDITION) AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N 47°56'E 56.84' NAIL AND TAG IN SOUTHEAST SIDE DE POLE, FOUND (SUPRA)

S 38°38'E 42.72' SET NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN SOUTHWEST SIDE DE POLE

N 02°28'E 45.70' SET NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN WEST SIDE 24" MAPLE TREE

S 15°30'W 109.07' SET NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN TWIN 18" OAK TREES (SUPRA)

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON 1/2" REROD B-11

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

2R
11/1/93