

RC 1279

LI27033 PA 850

SURVEY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE COUNTY
(County)

Located In:
TWP. OF CANTON

Corner Code ##

- 1. Public Land Survey T 2S R 8E C-2
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-93 *DOJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1800's) DESCRIPTION OF CORNER NOT STATED IN NOTES

WITNESSES: POPLAR S16E 35 (23.10') (GONE)
WO 60 N8E 14 (9.24') (GONE)

W.P.A. (1930's) MON. (#16)

- NNE 55.28' MON (MEAS. 55.84')
- NE 62.86' NAIL IN 22" MAPLE (MEAS. 62.75')
- SE 79.25' NAIL IN 24" SPRUCE (GONE)
- SW 91.92' NAIL IN 18" ELM (GONE)
- NW 29.94' NAIL IN 30" MAPLE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO C-3 MEASURED AS 2653.43'; RECORDED WPA (1930's) 2653.71'

L.17738 P.435 FOUND MONUMENT 1971 (CS)

- NW 59.81' NAIL AND WAYNE COUNTY ROAD COMMISSION TAG NORTHEAST SIDE 24" MAPLE
- NE 60.51' VERT. NAIL AND WAYNE COUNTY ROAD COMMISSION TAG SOUTHWEST ROOT 24" MAPLE (FOUND 60.50')
- SE 79.20' SPIKE SOUTHWEST SIDE 30" SPRUCE (THIS IS OLD WAYNE COUNTY ROAD COMMISSION WITNESS) (GONE)

L.17738 P.436 STEEL ENCASED CONCRETE MONUMENT 1971 (RC)

- NW 59.81' NAIL AND WAYNE COUNTY ROAD COMMISSION TAG NORTHEAST SIDE 24" MAPLE
- NE 60.51' VERT. NAIL AND WAYNE COUNTY ROAD COMMISSION TAG SOUTHWEST ROOT 24" MAPLE (MEAS. 60.50')
- SE 79.20' SPIKE SOUTHWEST SIDE 30" SPRUCE (OLD WITNESS) (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SECTION 1/4 CORNER 5 AND 6 T2S, R8E

FOUND 1" PIPE IN STEEL ENCASED CONCRETE MONUMENT 0.50' BELOW ROAD (GRAVEL) AT RIDGE ROAD AND GYDE ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

RECORDED IN THE REGISTER OF DEEDS
OFFICE OF THE REGISTER OF DEEDS
WAYNE COUNTY, MICHIGAN
NOV 10 1993

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											



Signed by *E. Patrick O'Rourke*
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

2R

SECTION B (CONTINUED)

L.18444 P.866 NO DESCRIPTION ON CS

- N 20°W 29.94' NAIL IN MAPLE (GONE)
- N 50°E 62.86' NAIL IN MAPLE (MEAS. 62.75')
- S 45°E 31.30' NAIL IN UTILITY POLE (GONE)
- DUE W 29.90' NAIL IN UTILITY POLE (GONE)

L.18444 P.849 RC (1973) MONUMENT

- NW 59.81' NAIL IN 24" MAPLE
- NE 60.51' NAIL IN SOUTHWEST ROOT IN 24" MAPLE (FOUND 60.50')
- SE 79.20' SPIKE IN 30" SPRUCE (GONE)

- N 50°E 62.86' NAIL IN MAPLE
- S 45°E 31.10' NAIL IN UTILITY POLE (GONE)
- DUE W 29.90' NAIL IN UTILITY POLE (GONE)
- N 20°W 29.94' NAIL IN MAPLE (GONE)

L.21473 P.352 1" IRON PIPE IN CONCRETE MONUMENT (RC)

- N 45°W 31.29' NAIL IN 16" MAPLE (FOUND MEAS. 31.45')
- N 45°E 62.23' NAIL IN 24" MAPLE (FOUND MEAS. 62.75')
- S 20°W 79.25' NAIL IN 24" SPRUCE (GONE)
- S 50°W FENCE POST

- NW 59.81' NAIL IN 24" MAPLE
- NE 60.51' NAIL IN 24" MAPLE (FOUND MEAS. 60.50')
- SE 79.20' NAIL IN 30" SPRUCE (GONE)

FILE DO NOT MAIL

L.20383 P.856 FOUND CONCRETE MONUMENT (1978)

- N 30°E 53.65' ROAD NAME SIGN (GONE)
- N 40°E 60.51' NAIL IN 24" RED MAPLE (MEAS. 60.50')
- S 45°E 31.00' STEEL FENCE POST (MEAS. 30.98')
- N 50°W 30.71' NAIL IN 18" RED OAK (GONE)

SECTION C (CONTINUED)

WITNESSES: NE 55.84' STEEL ENCASED CONCRETE MONUMENT

- NE 62.75' NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN SOUTHEAST SIDE 24" TREE
- NE 60.50' VERT NAIL AND WAYNE COUNTY ROAD COMMISSION TAG IN SOUTHWEST ROOT 24" TREE
- NE 51.63' SOUTHEAST CORNER ROAD SIGN
- SE 30.98' "X" IN CONCRETE BASE STEEL FENCE CORNER OF CEMETERY
- NW 30.27' P.K. NAIL AND WAYNE COUNTY ROAD COMMISSION TAG SOUTH SIDE 30" TREE
- NW 31.45' NAIL IN NORTHEAST SIDE 30" TREE
- W 29.67' NAIL AND TAG RLS #10705 SOUTH SIDE 10" TREE
- W 29.78' P.K. IN SOUTH SIDE 10" TREE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE 1" PIPE C-2.

12/13/93 35696 DEED 14.00
 12/13/93 35696 REMO FEE 2.00