

RC 1280

L127033 PA 852

FEB 26 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: WAYNE (County), Located In: TWP. OF CANTON, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at row 7, column C.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (1818) DESCRIPTION OF CORNER NOT STATED IN NOTES.
WITNESSES: SUGAR 18 S13W 25 (16.50') (GONE)
DO 19 N79E 35 (23.10') (GONE)
WPA (1930's) CROSS NW-20 (#89)
WITNESSES: NE 78.68' 4" TREE (GONE)
SE 43.62' EDISON POLE (GONE)
NW 86.00' 4" ELM (GONE)
NE 45.05' NAIL EAST SIDE GUY POLE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- DISTANCE TO D-7 MEASURED AS 2675.37'; RECORDED WPA (1930) MEASURED AS 2675.27' AND 2675.88';
DISTANCE TO C-8 MEASURED AS 2640.38'; RECORDED WPA (1930) MEASURED AS 2640.24' AND 2640.66'
L.18102 P.549 FOUND IRON (1972)
N 40°E 38.87' SUPPORT POLE
N 70°W 86.00' 10" TREE (GONE)
S 40°W 40.30' SIGN BASE (GONE)
S 25°E 46.14' UTILITY POLE (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- NORTHWEST CORNER SECTION 20 FOUND 1/2" REROD IN CONCRETE IN ROAD BOX 1.35' BELOW ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 13°01'W 32.73' NAIL IN WEST SIDE MBT POLE
N 37°47'E 38.82' P.K. NAIL IN SOUTHWEST SIDE GUY POLE (PREVIOUSLY USED)
S 55°26'E 45.73' P.K. NAIL IN NORTHEAST SIDE UTILITY POLE
S 72°37'W 105.56' P.K. NAIL IN NORTH SIDE DE POLE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND REROD.

Signed by [Signature]
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993



Handwritten initials/signature at the bottom right.

12/13/93 35696 DEED 14.00  
12/13/93 35696 REMO FEE 2.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

- L.18840 P.453 FOUND CONCRETE MON. IN BOX (1974)
  - N 40°E 38.95' P.K. NAIL IN POLE (MEAS. N 37°47'E 38.82')
  - S 20°E 46.15' P.K. NAIL IN POLE (GONE)
  - S 05°W 107.39' P.K. NAIL IN POLE (GONE)
  
- L.18946 P.453 FOUND CONCRETE MON. IN BOX (1974)
  - N 40°E 38.95' P.K. NAIL IN POLE (MEAS. N 37°47'E 38.82')
  - S 20°E 46.15' P.K. NAIL IN POLE (GONE)
  - S 05°W 107.39' P.K. NAIL IN POLE (GONE)