

RC 1281

L127033 PA 854

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in GOVERNMENT

WAYNE (County)	Located In: TWP. OF CANTON	Corner Code =#
1. Public Land Survey	T <u>2S</u> R <u>8E</u>	C-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-93 *[Signature]*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES.

WITNESSES: SUGAR 6" N79E 6 (3.96')(GONE)
IRON'D 4" S51W 13 (8.58')(GONE)

(CONTINUED ON OTHER SIDE)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO EAST 1/4 CORNER SECTION 30 MEASURED AS 2635.91'; RECORDED WPA 1930 DISTANCES 2635.98' AND 2635.93';
DISTANCE TO SOUTH 1/4 CORNER SECTION 29 MEASURED AS 2652.80'; RECORDED WPA 1930 DISTANCE 2652.25';
DISTANCE TO SOUTH 1/4 CORNER SECTION 30 MEASURED AS 2678.88'; RECORDED WPA 1930 DISTANCE 2677.81 AND 2636.85';

L.17986 P.302 FOUND MONUMENT IN BOX (1972)

NE 47.60' ROAD SIGN (GONE)
SE 47.79' SPIKE IN NORTHEAST SIDE DE POLE (GONE)
NW 44.10' NAIL & CAP SOUTHWEST SIDE MBT POLE (MEAS. 43.99')

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 SOUTHEAST CORNER SECTION 30 - SOUTHWEST CORNER SECTION 29 T2S, R8E
FOUND 3/8" REROD IN MON. BOX CENTERLINE GEDDES AND DENTON ROADS AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: S 55°20'E 61.24' P.K. NAIL IN TAG SOUTHWEST SIDE DE POLE (PREVIOUSLY USED)
S 31°13'N 69.24' P.K. NAIL IN TAG NORTHWEST SIDE 18" BLACK WALNUT (PREVIOUSLY USED)
N 62°23'W 71.61' NAIL IN TAG SOUTHWEST SIDE ALERT SIREN POLE
N 46°09'W 43.65' P.K. NAIL IN TAG NORTHEAST SIDE MBT POLE (PREVIOUSLY USED)

PLACED REMONUMENTATION BRASS TAG & CAP #16937 ON REROD.

Signed by *[Signature]*
Surveyor's Michigan License No. E. PATRICK O'ROURKE 16937

Date DECEMBER 7, 1993

2K

u27033pa855

12/13/93 35696 DEED 14.00
12/13/93 35696 REMO FEE 2.00

SECTION A (CONTINUED)

WPA 1930's - STONE #141

WITNESSES: NE 40.06' CORNER FENCE POST (GONE)
SE 43.41' 20" MAPLE (GONE)
SW 85.36' 14" APPLE (GONE)
SW 98.85' EDISON POLE (GONE)
NW 20.46' FACE STOP SIGN (GONE)

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.17986 P.311 FOUND MONUMENT IN BOX (1972)

NE 47.60' ROAD SIGN (GONE)
SE 47.79' SPIKE IN NORTHEAST SIDE DE POLE (GONE)
NW 44.10' NAIL AND CAP SOUTHWEST SIDE MBT POLE (MEAS. 43.99')

L.18946 P.463 FOUND CONCRETE MONUMENT IN BOX (1974)

SE 60.25' P.K. NAIL IN DE POLE (GONE)
SW 69.30' NAIL AND TAG IN 12" BLACK WALNUT (MEAS. 69.24')
NW 43.50' P.K. NAIL IN MBT POLE (MEAS. 43.65')

L.20805 P.399 FOUND CONCRETE MONUMENT IN BOX (1979)

SE 60.90' NAIL IN DE POLE (MEAS. 61.24')
SW 69.05' NAIL IN 18" BLACK WALNUT (MEAS. 69.24')
SW 100.88' NAIL IN DE POLE (GONE)
NW 44.05' TAG AND NAIL IN MBT POLE (MEAS. 43.65)