

FEB 28 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A.1970

SECTION

FILE DO NOT MAIL

For corners in

WAYNE
(County)

Located In: CANTON

Corner Code # E-2

Liber-30821 Page-46
99588862 12/22/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-99
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File
Number

- 1. Public Land Survey T 2S R 8E CANTON TWP(07)
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, PETER P. PALCZYNSKI, P.S. in a field survey on 1 DEC, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-2
1816 GLO: SET POST BEECH 6" S62W 7 LKS.
JOSEPH FLETCHER DO 15" N8E 15 LKS
SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E-2
FD 3/8" STEEL BAR IN CONCRETE MONUMENT / MON BOX @ CENTERLINE INTERSECTION OF BECK & GYDE RDS. (30' WD ASP PVT). PLACED PLASTIC CAP "PPP-PS 30096" / WCR BRASS WASHER ON 3/8" STEEL BAR IN CONC MON / MON BOX. CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:

- E-2 / E-1 = 2651.65 (2651.86 & .09 WPA / 2651.39 PLAT)
- E-2 / E-3 = 2654.73 (2654.43 & .50 WPA / 2663.61 PLAT)
- E-2 / D-2 = 2670.57 (2670.57 WPA / 2670.57 PLAT)
- E-3 / E-2 / D-2 = 88 37' 12" (88 37' 00" WPA)
- D-2 / E-2 / E-1 = 91 59' 54" (91 59' 30" WPA)
- E-1 / E-2 / E-3 = 179 22' 54" (179 23' 00" WPA)

Description of monument for corner and accessories established to perpetuate locating the position of the corner: E-2
FD 3/8" STEEL BAR IN CONCRETE MONUMENT / MON BOX @ CENTERLINE INTERSECTION OF BECK & GYDE RDS. (30' WD ASP PVT). PLACED PLASTIC CAP "PPP-PS 30096" / WCR BRASS WASHER ON 3/8" STEEL BAR IN CONC MON / MON BOX.
CENTERLINE OF FIRE HYDRANT STEM N16E 146.62'
FD PK NAIL/WCRC REF PT TAG IN SOUTH FACE 24" HICKORY(10)(R=30.22') EAST 30.16'
FD PK NAIL/SQUARE WASHER IN EAST FACE UTILITY POLE(12)(R=97.40') S22E 97.30'
SET PK NAIL/AMBIT TAG IN NW FACE UTILITY POLE(11)(58.29') S34W 58.31'
SET PK NAIL IN NORTH FACE OF UTILITY POLE N78W 129.41'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by _____ Date 1 DEC 99

Surveyor's Michigan License No. 30096

2S8EE-2.DOC



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

R LCR 15 4R 3 Pgs A.
[Signature]

