

SURVEY & REMONUMENTATION

RC 1490

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:01 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

Table with columns: WAYNE (County), Located In: TOWNSHIP OF CANTON, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

L127797PA628

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numerical data for recording purposes.

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1815) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: ELM 14 S 69 W 29 (19.14 R) (GONE)
ELM 16 N 8 E 22 (14.52 R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
(CONTINUED ON BACK)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO D-13 TRAVERSED AND SET AT 2641.77'; RECORD WPA (1930) DISTANCE AS 2642.28'
DISTANCE TO E-12 TRAVERSED AND SET AT 2641.91'; RECORD WPA (1930) DISTANCE AS 2641.91'
DISTANCE TO F-13 TRAVERSED AND SET AT 2645.81'; RECORD WPA (1930) DISTANCE AS 2646.32'
E-13 SOUTHEAST CORNER SECTION 32, SOUTHWEST CORNER SECTION 33, T.2S., R.8E NO CORNER FOUND
SET 3/8" X 18" RE-ROD AS A TEMPORARY CORNER BY TRAVERSE FROM SOUTH 1/4 CORNER SECTION 32 TO SOUTH 1/4 CORNER SECTION 33. TRAVERSE DISTANCE CALCULATED 5287.58', DISTANCE FROM WPA (1930) 5288.60'; A SHORTAGE OF 1.02'. SUBTRACTED 0.51 FROM RECORD DISTANCE FROM SOUTH 1/4 CORNER SECTION 32 TO SOUTHEAST CORNER SECTION 32. RECORD WPA (1930) 2642.28'; SET AT 2641.77'. SUBTRACTED 0.51 FROM RECORD DISTANCE FROM SOUTH 1/4 CORNER SECTION 33 TO SOUTHEAST CORNER SECTION 32. RECORD WPA (1930) 2646.32', SET AT 2645.81'. SET RECORD DISTANCE FROM EAST 1/4 CORNER SECTION 32 TO SOUTHEAST CORNER SECTION 32. RECORD WPA (1930) 2641.91', SET AT 2641.91'.
NO L.C.R.C. OR CS ON FILE AT WAYNE COUNTY REGISTER OF DEEDS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 SECTION CORNER 32, 33 T.2S., R.10E.
SET CONCRETE MONUMENT WITH 3/8" RE-ROD IN LIGHTLY WOODED, SCRUB BRUSHED AREA SURROUNDED BY FARM LAND, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 01°10' E 27.51' NAIL/"WCRC" WASHER EAST SIDE 5, 6" ELMS
N 88°29' E 17.76' NAIL/"WCRC" WASHER NORTH SIDE 4" X 4" WOOD POST
S 01°34' W 5.39' NAIL/"WCRC" WASHER EAST SIDE 2" ELM
S 87°43' W 8.14' NAIL/"WCRC" WASHER NORTH SIDE 4" ELM

PLACED A MONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD.

Signed by [Signature] E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

Date 12-27-94

LI27797PA629

SECTION A (CONTINUED) WPA

(1930) STONE SW 33 #165

WITNESSES: NE 2.15 6" ASH (GONE)  
SE 48.70 16" HICKORY (GONE)  
WEST 472+/- STAKE (MEASURE 472.42)  
NW 10.10 5" TRIPLE ELM (GONE)  
NNW 25.17 8" TWIN ELM (GONE)

W.C.R.C. (1970) STONE SW 33 #165

WITNESSES: NORTH 97.06 40" ELM (GONE)  
EAST 68.76 DETROIT EDISON POLE (MEAS. 68.46)  
WEST 471.5+/- NE 5 VAN BUREN (MEAS. 472.42)