

FEB 28 1994

RC 1282

LI27033 PA 856

COMPLIANCE

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)	Located In: TWP. OF CANTON	Corner Code # 6-1
1. Public Land Survey	T 2S R 8E	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-93 *DP*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. DESCRIPTION OF CORNER NOT STATED IN NOTES.
 WITNESSES: SUGAR 7" S59E 7 (4.62') (GONE)
 IRON'D 5" WEST 7 (4.62') (GONE)
 WPA 1930's IRON #7

(CONTINUED ON OTHER SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO G-2 MEASURED AS 2587.69'; RECORDED WPA 1930 DISTANCES 2586.71' AND 2587.07';
 DISTANCE TO N 1/4 CORNER 3 MEASURED AS 2646.16'; RECORDED WPA 1930 DISTANCE 2645.90';
 DISTANCE TO N 1/4 CORNER 4 MEASURED AS 2607.24'; RECORDED WPA 1930 DISTANCE 2606.10'

L.17923 P.84 FOUND MON. IN BOX (1971)
 NE 45.28' P.K. NAIL SOUTHEAST SIDE DE POLE (MEAS. 45.06')
 SW 73.84' P.K. NAIL SOUTHEAST SIDE MBT POLE (MEAS. 74.03')
 NW 38.06' CROSS TOP WITH END 48" STORM SEWER% (MEAS. 38.12')

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 NORTHEAST CORNER SECTION 5 - NORTHWEST CORNER SECTION 3 T2S, R8E
 FOUND 1/2" REROD IN MON. BOX IN WEST BOUND LANE OF JOY ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N 44°22'E 45.03' NAIL & SHINER NORTHWEST SIDE UTILITY POLE (PREVIOUSLY USED)
 S 52°52'E 65.15' "X" CHISELED IN TOP OF NORTHWEST CORNER OF WALK/DON'T WALK LIGHT POST
 S 43°48'W 74.16' NAIL & SHINER SOUTHEAST SIDE U.P. (PREVIOUSLY USED)
 N 51°30'W 38.12' "X" IN TOP OF WEST END 48" CONCRETE CURB (PREVIOUSLY USED)

PLACED REMONUMENTATION BRASS TAG & CAP #16937 ON REROD

Signed by *E. Patrick O'Rourke*
 E. PATRICK O'ROURKE
 Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993



2R

LI 27033 PA 857

12/13/93 35696 REMO FEE 2.00
12/13/93 35696 DEED 14.00

SECTION A (CONTINUED)

WITNESSES: NE 37.87' CB COVER (GONE)
EAST 103.00' CORNER FOR PLYMOUTH REROD IN MSDH (MEAS. 102.92')
SE 7.49' IRON (GONE)
SE 72.65' CROSS ON ROAD SIGN (GONE)
SW 46.98' GUY POLE (GONE)
NW 26.98' CROSS ON BUILDING BASE (GONE)

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.18605 P.73 FOUND 1/2" IRON IN BOX (1973)

NE 44.82' NAIL IN UTILITY POLE (MEAS. 45.06')
SW 73.91' NAIL IN UTILITY POLE (MEAS. 74.03')
NW 38.10' "X" IN CONCRETE CULVERT (MEAS. 38.12')

L.20027 P.884 CONCRETE MON. IN BOX (1978)

NE 45.18' SPIKE WITH BRASS TAG NORTHWEST SIDE DE POLE (MEAS. 45.03')
SW 73.95' SPIKE WITH BRASS TAG SOUTHEAST SIDE MBT POLE (MEAS. 74.16')
NW 44.99' SPIKE WITH BRASS TAG NORTHEAST SIDE 18" BOX ELDER (GONE)
SE 54.11' "X" CUT ON NORTHWEST BOLT OF MOBIL SIGN BASE (GONE)

L.22560 P.79 FOUND 1/2" REROD IN MON. BOX (1985)

NE 45.12' NAIL & SHINER NORTHWEST SIDE UTILITY POLE (MEAS. 45.03')
NE 29.20' NAIL IN WEST SIDE GUARD RAIL POST (GONE)
SW 73.90' NAIL & SHINER SOUTHEAST SIDE U.P. (MEAS. 74.16')
NW 45.00' NAIL & SHINER NORTHEAST SIDE 20" TREE (GONE)