

SURVEY & REMONUMENTATION

RC 1491

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA630

For corners in

WAYNE (County)	Located In: TOWNSHIP OF CANTON #07	Corner Code ##
1. Public Land Survey	T 2S R 8E	G-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-7-94 DBJ
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1491

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, E. PATRICK O'ROURKE, in a field survey on OCT. 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
WITNESSES: BEECH 9 N 35 E 25 (16.50 R) (GONE)
BEECH 18 S 2 E 15 (9.90 R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE IN CONCRETE MONUMENT ON CENTERLINE OF YOST ROAD AT TOP OF GRAVEL SURFACE.
DISTANCE TO H-13 MEASURED AS 2645.15'; RECORD WPA (1930s) DISTANCE OF 2645.40'
DISTANCE TO G-12 MEASURED AS 2634.35'; RECORD WPA (1930s) DISTANCES OF 2634.51' AND 2633.73'
L.18661 P.552-553 FOUND CONCRETE MONUMENT IN BOX (1973) CS #786
N 80° E 136.18 DETROIT EDISON POLE (MEASURED 139.39)
S 30° W 55.13 DETROIT EDISON POLE (MEASURED 54.77)
N 25° W 31.87 DETROIT EDISON POLE (MEASURED 32.06)

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:01 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 SE CORNER SECTION 33, SW CORNER SECTION 34 T.2S, R.8E
FOUND 1/2" IRON PIPE IN CONCRETE MONUMENT ON CENTERLINE YOST ROAD AT TOP OF GRAVEL SURFACE, AND ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 83°05' E 139.39 NAIL/SHINER SOUTH SIDE UTILITY POLE (PREVIOUSLY USED)
S 55°48' W 54.77 NAIL/SHINER NORTH SIDE UTILITY POLE (PREVIOUSLY USED)
N 44°36' W 59.82 CENTERLINE TOP HYDRANT (PREVIOUSLY USED)
N 0°54' W 32.06 NAIL/SHINER WEST SIDE UTILITY POLE (PREVIOUSLY USED)

PLACED REMONUMENTATION BRASS TAG AND CAP #16937 ON PIPE.



Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

LI27797PA631

SECTION A (CONTINUED)

WPA (1930s) IRON SW 34 #163

WITNESSES:	NORTH 46.00	24" ELM STUMP (GONE)
	NE 136.03	EDISON POLE (MEASURED 139.39)
	SW 85.20	3" ELM (GONE)
	WEST 467' +/-	IRON
	NW 33.55	EDISON POLE (MEASURED 32.06)

W.C.R.C. (1970) MONUMENT SW 34 #163

WITNESSES:	NW 59.71	TOP OF HYDRANT (MEASURED 59.82)
	NE 136.40	RR SPIKE DETROIT EDISON POLE (GONE)
	SW 55.03	MICHIGAN BELL TELEPHONE POLE (MEASURED 55.13)