

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
WAYNE (County)

Table with columns: Located In: TWP. OF CANTON, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-93 [Signature]
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column D and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (1818-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES
WITNESSES: IRON W'D 9 S49W 10 (6.60') (GONE)
CHERRY 12 S58E 10 (6.60') (GONE)
WPA (1930's) IRON PIPE OVER STONE #136
WITNESSES: NW 42.30' MAPLE (GONE)
EAST 10.85' FENCE (GONE)
SE 61.50' NORTH BRICK COLUMN OF PORCH (MEAS. 61.25')
SW 59.75' ROOT OF 24" LOCUST (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- DISTANCE TO H-10 MEASURED AS 2654.28'; RECORDED WPA (1930) AS 2654.59'
DISTANCE TO H-12 MEASURED AS 2674.46'; RECORDED WPA (1930) AS 2647.09'
L.18859 P.478 FOUND CONCRETE MONUMENT (1974)
SE 32.88' FOUND IRON (MEAS. 32.80')
SE 61.44' NORTH BRICK COLUMN OF PORCH (MEAS. 61.25')
SW 59.58' NAIL NORTH SIDE ROOT 24" LOCUST (GONE)
NW 33.00' FOUND IRON (MEAS. 33.17')
NW 42.09' NAIL SOUTH SIDE 24" MAPLE (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-11 SOUTH 1/4 CORNER SECTION 27 - FOUND 3/8" REROD IN CONCRETE MON. IN MON. BOX AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- WITNESSES: S 63°19'E 61.25' NORTHWEST CORNER BRICK PORCH PILLAR OF HOUSE #3725 (PREVIOUSLY USED)
S 27°27'W 83.69' FORM NAIL IN SOUTHEAST SIDE 20" OAK (PREVIOUSLY USED)
S 71°38'W 36.64' GLA PLASTIC CAP SOUTH SIDE UTILITY POLE
N 60°31'W 91.37' SOUTHEAST CORNER HOUSE #3704 (PREVIOUSLY USED)

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON MONUMENT H-11

[Handwritten signature of E. Patrick O'Rourke]

Signed by E. PATRICK O'ROURKE

DECEMBER 7, 1993

Date

Surveyor's Michigan License No. 16937



2K

LI 27033 PA 865

12/13/93 35696 REMO FEE 2.00
12/13/93 35696 DEED 14.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.24765 P.441 (1990)

EAST	32.88'	FOUND IRON PIPE (MEAS. 32.80')
SE	61.48'	NORTH BRICK COLUMN OF PORCH HOUSE #3725 (MEAS. 61.25)
SW	83.91'	FOUND FORM NAIL IN SOUTHEAST FACE OF 20" OAK TREE (MEAS. 83.69')
SW	36.49'	FOUND P.K. NAIL IN NORTH FACE OF UTILITY POLE (MEAS. 36.42')
WEST	33.13'	FOUND CONCRETE MONUMENT (MEAS. 33.17')
NW	91.34'	SOUTHEAST CORNER OF HOUSE #3704 (MEAS. 91.37')