

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located in: TOWNSHIP OF CANTON (#07)	Corner Code # _____
1. Public Land Survey	T <u>2S</u> R <u>8E</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **29337** PAGE **568**

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-13-96
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, **WALTER J. ZBIKOWSKI**, in a field survey on **OCTOBER 14, 1996**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, remonumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
 G.L.O. (1819), NORTH 80.00 CHAINS, SET POST COR SECS 14, 15, 22, 23 (DESCRIPTION OF CORNER NOT STATED IN NOTES)
 WITNESSES: BEECH 10" S 26 E 5 (LINKS) (3.30') (GONE)
 W.O. 38" N 78 W 8 (LINKS) (5.28') (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
 W.P.A. (1930's), IRON SET, NW-23 (#83)
 WITNESSES: NE 58.88' 8" MAPLE (GONE)
 SE 90.40' TELEPHONE POLE BRACE (GONE)
 SW 47.98' TELEPHONE POLE (GONE)
 NW 56.30' 3" ELM (GONE)

\$ 7.00 DEED
\$ 4.00 REMONUMENTATION
12 DEC 96 2:15 P.M. RECEIPT# 62B
 RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
 FOUND A 3/8" REBAR IN A ROAD BOX (GOOD, WITHOUT LID) AT THE INTERSECTION OF CHERRY HILL ROAD (A TWO LANE ASPHALT ROAD) AND MORTON TAYLOR ROAD (UNIMPROVED).

DISTANCE TO J-7 MEASURED AS 2619.30'; G.L.O. (1819) RECORD DISTANCE OF 39.60 CHAINS (2613.60'); W.P.A. (1930's) RECORD DISTANCES OF 2618.94' AND 2619.16';
 DISTANCE TO H-7 MEASURED AS 2651.42'; G.L.O. (1819) RECORD DISTANCE OF 39.92-1/2 CHAINS (2635.05'); W.P.A. (1930's) RECORD DISTANCE OF 2652.29';
 L.18836, P.325-326, FOUND MONUMENT IN HANDHOLE (1974) RC #337
 WITNESSES: N.47°28'00"E. 55.06' NAIL IN W. SIDE 18" MAPLE (GONE)
 S.09°02'00"E. 36.39' NAIL IN W. SIDE DETROIT EDISON POLE (GONE)
 S.41°00'00"W. 42.88' NAIL IN ?? SIDE 10" MAPLE (GONE)
 N.59°49'00"W. 61.85' NAIL IN NE SIDE OF DETROIT EDISON POLE (GONE)

L.20102 P. 661-664, FOUND RE-ROD IN MONUMENT BOX (1978) CS #1476
 WITNESSES: N.20°E. 78.53' PK NAIL IN (SE/S) OF UTILITY POLE (GONE)
 SOUTH 60.00' FOUND IRON PIPE (GONE)
 N.45°W. 75.22' PK NAIL (NE/SIDE) OF UTILITY POLE (MEASURED 75.20')

L.25009, P. 61, FOUND RE-ROD IN MONUMENT BOX (1990) RC #995
 WITNESSES: SOUTH 32.96' 3/4" PIPE (GONE)
 SW 75.19' PK NAIL IN WASHER E. SIDE POWER POLE (MEASURED 75.17')
 NW 75.20' PK NAIL (DOUBLE HEAD NAIL) IN WASHER ON SW. SIDE POWER POLE (MEASURED 75.21')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
 I-7, SECTION CORNER 14, 15, 22, AND 23. R.2S., R.8E.

PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #21586 ON 3/8" REBAR IN A ROAD BOX AT THE INTERSECTION OF CHERRY HILL ROAD (A TWO LANE ASPHALT ROAD) AND MORTON TAYLOR ROAD (UNIMPROVED) AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N.23°47'E. 104.47' TIP OF ARROW ON TOP NUT OF FIRE HYDRANT
 N.47°58'E. 113.08' SOUTHEAST CORNER OF BLOCK FOUNDATION TO HO USE #43412 CHERRY HILL ROAD
 S.45°21'W. 75.17' FOUND PK NAIL IN PLAIN DISC ON NE SIDE OF POWER POLE (SUPRA)
 N.48°16'W. 75.21' FOUND NAIL IN GW ALUMINUM DISC ON SW SIDE OF POWER POLE

Signed by Walter J. Zbikowski Date Dec. 11, 1996
 WALTER J. ZBIKOWSKI
 Surveyor's Michigan License No. 21586

10027000

48
70
M