

**SURVEY &
REMONUMENTATION**

APR 25 1995

RC 1492

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LI27797PA632

For corners in

WAYNE (County)	Located In: TOWNSHIP OF CANTON	Corner Code #
1. Public Land Survey	T 2S R 8E	I-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-7-94 *DOJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

RC 1492

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: ASH 14 WEST 11 (7.26' R) (GONE)
ASH 7 N 64 E 5 (3.30' R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:01 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE, 6" +/- BELOW GRAVEL SURFACE OF ROAD INTO JUNK YARD.
DISTANCE TO J-13 MEASURED AS 2676.04'; RECORD WPA (1930) DISTANCE OF 2676.37'
DISTANCE TO H-13 MEASURED AS 2631.52'; RECORD WPA (1930) DISTANCE OF 2631.66'
L.20325 P.653 3/4" IRON PIPE
N 20° E 25.11 NAIL IN POWER POLE (MEASURED 25.28)
N 70° W 148.56 NAIL IN POWER POLE (MEASURED 148.60)
S 45° E 28.69 NAIL IN 10" WALNUT (MEASURED 28.75)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 SE CORNER SECTION 34, SE CORNER SECTION 35, T.2S., R.8E
FOUND 3/4" IRON PIPE, 6" +/- BELOW GRAVEL SURFACE OF ROAD INTO JUNK YARD, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 20° E 25.28 NAIL/SHINER SOUTHEAST SIDE UTILITY POLE (PREVIOUSLY USED) (W.C.R.C.TAG)
N 70° W 148.60 NAIL/SHINER SOUTHWEST SIDE UTILITY POLE (PREVIOUSLY USED) (W.C.R.C.TAG)
S 45° E 28.75 NAIL/SHINER NORTHEAST SIDE 20" WALNUT (PREVIOUSLY USED) (W.C.R.C.TAG)
S 88° W 26.00 NAIL/SHINER WEST SIDE 6" MULTI-STEMMED TREE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON 3/4" IRON PIPE

Signed by *E. Patrick O'Rourke* Date Dec. 27, 1994
Surveyor's Michigan License No. 16937

L127797PA83

SECTION A (CONTINUED)

W.P.A. (1930s) IRON SW 35 #161

WITNESSES: NE 25.69 EDISON POLE (MEASURED 25.28)
SE 28.75 8" WALNUT (MEASURED 28.75)
SE 50.26 6" ELM (GONE)
SW 34.51 36" ELM (GONE)
WEST 442' +/- IRON

W.C.R.C. (1970s) IRON SW 35 #161

WITNESSES: NE 25.09 DETROIT EDISON POLE (MEASURED 25.28)
SE 28.75 16" WALNUT (MEASURED 28.75)
NW 148.68 DETROIT EDISON POLE (MEASURED 148.60)