

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 29337 PAGE 560

For corners in

WAYNE
(County)

Located in: Corner Code #
TOWNSHIP OF CANTON (#07)

1. Public Land Survey	T2S R8E	J-5
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-13-96
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30										25
11											
12	31										36
13											

I, WALTER J. ZBIKOWSKI, in a field survey on OCTOBER 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.
ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
 G.L.O. (1819), WEST, CORRECTED BETN S, 11-14, 39.50 CHAINS, SET 1/4 S. POST AT AV. DIST. (DESCRIPTION OF CORNER NOT STATED IN NOTES)
 WITNESSES: ASH 11" S.53E. 11 (LINKS) (7.26') (GONE)
 ELM 28" N73W 15 (LINKS) (9.90') (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
 W.P.A. (1930's), CROSS, N-14 (#56)
 WITNESSES: NE 45.98' 14" WALNUT (GONE)
 SE 42.11' 24" TRIPLE MAPLE (GONE)
 SW 38.77' CROSS ON CON. RD. SIGN (GONE)
 NW 44.07' 18" ELM (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
 FOUND 1/2" PINCHED IRON IN CONCRETE MONUMENT IN A ROAD BOX (GOOD, WITHOUT LID) AT THE INTERSECTION OF FORD ROAD (A FIVE LANE ASPHALT SURFACED ROAD) AND LILLEY ROAD (A FOUR LANE ASPHALT SURFACE ROAD)
 DISTANCE TO K-5 MEASURED AS 2609.60'; G.L.O. (1819) RECORD DISTANCE OF 39.50 CHAINS (2607.00'); W.P.A. (1930's) RECORD DISTANCE OF 2609.12'; L.20708, P.31, CS #1627 (1979) RECORD DISTANCE OF 2609.70';
 DISTANCE TO J-6 MEASURED AS 2643.24'; W.P.A. (1930's) RECORD DISTANCE OF 2643.00';
 DISTANCE TO I-5 MEASURED AS 2624.36'; G.L.O. (1819) RECORD DISTANCE OF 39.50 CHAINS (2607.00'); W.P.A. (1930's) RECORD DISTANCE OF 2624.39';
 L.18076, PG. 780-781, IRON PIPE IN MONUMENT BOX (1972) CS #172
 WITNESSES: N.55°E. 56.70' UTILITY POLE (GONE)
 N.55°W. 60.90' UTILITY POLE (GONE)
 N.40°W. 61.70' W.C.R.C. BENCH MARK (GONE)
 N.35°W. 39.70' STREET SIGN (GONE)

\$ 10.00 DEED
 12 DEC 96 2:15 P.M. RECEIPT# 62B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
 J-5, SECTION CORNER 11, 15 T.2S., R.8E.
 PLACED A REMONUMENTATION BRASS DISC AND PVC CAP #21586 ON 1/2" IRON IN CONCRETE MONUMENT IN THE ROAD BOX (GOOD) AT THE INTERSECTION OF FORD ROAD (A FIVE LANE ASPHALT SURFACED ROAD) AND LILLEY ROAD (A FOUR LANE ASPHALT SURFACE ROAD) AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N.44°43'E. 69.98' FOUND NAIL IN KSW #21584 BRASS DISC ON WEST SIDE OF UTILITY POLE
 S.28°22'E. 72.17' FOUND CHISELED "X" IN NW BOLT ON BASE OF STEEL LIGHT POLE
 S.35°38'W. 78.88' FOUND PK NAIL ON EAST SIDE OF POWER POLE
 N.43°41'W. 69.75' FOUND NAIL IN MSHD BRASS DISC ON SW SIDE POWER POLE (SUPRA)

Signed by Walter J. Zbikowski Date DEC. 11, 1996
 WALTER J. ZBIKOWSKI
 Surveyor's Michigan License No. 21586

46
100
M

B. CONTINUED

L.18986 P.92, IRON PIPE IN HANDHOLE (1974) CS #1038

WITNESSES:	NE	56.70'	UTILITY POLE (GONE)
	S	90.00'	PK NAIL (GONE)

L.20245 PG. 383-384, FOUND MONUMENT BOX (1978) RC #614

WITNESSES:	N.60°E	57.06'	MICHIGAN BELL TELEPHONE POLE (GONE)
	S.45°W.	68.52'	NAIL AND TAG IN DETROIT EDISON POLE (GONE)
	N.45°W.	69.20'	NAIL AND TAG IN DETROIT EDISON POLE (MEASURED 69.75')

L.20965, P.143, IRON IN MONUMENT BOX (1980) RC #733

WITNESSES:	S.45°E.	53.47'	NAIL AND TAG IN POWER POLE (GONE)
	S.45°W.	67.93'	PK NAIL IN POWER POLE (GONE)
	N.45°W.	69.06'	PK NAIL IN POWER POLE (MEASURED 68.97')

FILE DO NOT MAIL