

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WAYNE

COMMISSION

	Located In:			Corner Code #
	TWP. OF CANTON			
1. Public Land Survey	T 2S	R 8E		K-12
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-93 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1288

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES

WITNESSES: ELM 22 S83-1/2E 6 (3.96') (GONE)
BEECH 20 N81W 35 (23.10') (GONE)

WPA 1930's IRON #154

WITNESSES: NE 29.60' 30" STUMP (GONE)
EAST 40.22' FENCE POST (GONE)
SE 59.84' 30" MAPLE (GONE)
WEST 33.97' 8' DOUBLE MAPLE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO NORTHEAST CORNER SECTION 35 MEASURED AS 2637.65'; RECORDED WPA 1930 DISTANCE 2637.15' AND 2637.38'
TO CENTER OF MON. BOX - NO IRON IN BOX

DISTANCE TO SOUTHEAST CORNER SECTION 35 MEASURED AS 2646.50'; RECORDED WPA 1930 DISTANCE 2646.45' AND 2646.54'
L.18107 P.80 FOUND 1/2" IRON PIPE (1972)

NE 58.21' DISC 19001 IN SOUTHEAST SIDE 7" OAK TREE (GONE)
EAST 72.83' DISC 19001 IN NORTH SIDE 6" OAK TREE (GONE)
NNW 61.90' DISC 19001 IN NORTHEAST SIDE UTILITY POLE (GONE)

L.18569 P.329 DESCRIPTION NOT GIVEN (1973)

N 40°40'E 53.30' RR SPIKE IN TREE (GONE)
N 86°23'E 72.30' PK NAIL IN TREE (GONE)
N 27°22'E 61.67' PK NAIL IN U.P. (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 EAST 1/4 CORNER SECTION 35

FOUND 1/2" IRON IN CONCRETE MONUMENT IN GRAVEL SHOULDER 3'+/- EAST OF EAST EDGE HAGGERTY ROAD AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N 24°08'E 88.43' P.K. IN NORTHWEST SIDE 15" ELM TREE (PREVIOUSLY USED)
N 64°31'E 43.88' "X" CUT IN WEST EDGE MANHOLE FRAME (PREVIOUSLY USED)
N 86°55'E 91.54' CENTERLINE TOP FIRE HYDRANT (PREVIOUSLY USED)
S 86°50'W 4.52' + OF STATION STENCIL 681-00 (PREVIOUSLY USED)
N 35°34'W 120.41' P.K. NORTHEAST SIDE UTILITY POLE

PLACED REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE 1/2" IRON K-12

Signed by *E. Patrick O'Rourke*
E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



RECORDED
INDEXED
MAY 14 1994

2R

12/13/93 35696 REMO FEE 2.00
 12/13/93 35696 DEED 14.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.18840 P.460 IRON PIPE (1974)

N 50°E	58.10'	P.K. NAIL IN 8" OAK (GONE)
N 85°E	91.54'	FIRE HYDRANT (MEAS. 91.54')
EAST	99.50'	P.K. NAIL IN 30" TREE (GONE)
N 20°W	61.90'	RR SPIKE IN POLE (GONE)

L.18859 P.647 FOUND IRON PIPE (1974)

N 51°53'E	58.06'	BRASS DISC SOUTHEAST SIDE 7" OAK (GONE)
N 89°43'E	72.60	BRASS DISC SOUTHEAST SIDE 6" OAK (GONE)
N 29°32'W	62.06'	BRASS DISC NORTHEAST SIDE UTILITY POLE (GONE)

L.19990 P.617 CONCRETE MON. IN GRAVEL SHOULDER (1977)

NE	88.28'	NAIL NORTHWEST SIDE 8" ELM (MEAS. 88.43')
NE	43.91'	"X" CUT IN WEST EDGE AND FRAME (MEAS. 43.88')
ESE	100.42'	NAIL SOUTH SIDE 24" STUMP (GONE)
WSW	91.04'	NAIL IN NORTH SIDE 9" ELM (GONE)
WEST	125.78'	NAIL WITH BRASS TAG SOUTH SIDE 15" TWIN MAPLE (GONE)

L.23835 P.356 CONCRETE MON. IN GRAVEL SHOULDER (1987)

N 35°E	88.42'	NAIL AND TAG IN 15" ELM (MEAS. 88.43')
N 80°E	43.96'	"X" CUT IN WEST EDGE MANHOLE RIM (MEAS. 43.88')
S 83°E	91.58'	TOP CENTER OF HYDRANT (MEAS. 91.54')
WEST	4.51'	"+" OF STATION STENCIL 681+00 (MEAS. 4.52')
N 80°W	26.89'	"X" IN WEST EDGE PAVEMENT (MEAS. 26.90')