

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE LI 27033 PA 869  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

WAYNE (County)	Located In: TWP. OF CANTON	Corner Code #
1. Public Land Survey	T 2S R 8E	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-10-93  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

RC 1289

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.

WITNESSES: ASH 24" S10W 7 (4.62') (GONE)  
BEECH 6" N18E 26 (17.16') (GONE)

WPA 1930's - IRON #159

WITNESSES SE 36.75' TELEPHONE POLE (GONE)  
SW 93.90' 28" ELM (GONE)  
W 54.33' IRON (MEAS. 54.32')  
NW 36.63' CROSS ON ROAD SIGN POST (GONE)  
NNW 34.25' POWER POLE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO EAST 1/4 CORNER SECTION 3S MEASURED AS 2646.50'; RECORDED WPA 1930 DISTANCE 2646.45 AND 2646.54;  
DISTANCE TO SOUTH 1/4 CORNER SECTION 3G MEASURED AS 2656.19'; RECORDED WPA 1930 DISTANCE 2655.61;  
DISTANCE TO SOUTH 1/4 CORNER SECTION 3S MEASURED AS 2607.41; RECORDED WPA 1930 DISTANCE 2606.95

L.18107 P.79 CENTER OF HANDHOLE (1972)

SE 37.45 MDSH REF. TAG WEST SIDE MBT POLE (GONE)  
W 54.30 CENTER OF HANDHOLE ON CENTER OF HAGGERTY ROAD TO SOUTH (MEAS. 54.32)  
NNW 34.34 DISC #19001 IN EAST SIDE DE POLE (GONE)

(CONTINUED ON OTHER SIDE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SOUTHWEST 1/4 CORNER SECTION 36 T2S, R8E

FOUND 1/2 IRON IN MONUMENT IN ROAD BOX AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

WITNESSES: N 25°55'E 52.83' NAIL & TAG WEST SIDE UTILITY POLE (PREVIOUSLY USED)  
S 3°39'E 89.64' NORTHWEST CORNER BUILDING  
S 65°11'W 119.59' NAIL & TAG SOUTHEAST SIDE UTILITY POLE  
N 64°02'W 116.81' P.K. NAIL NORTHEAST SIDE UTILITY POLE  
S 88°44'W 54.32' FOUND 1/2 IRON IN MON. BOX (PREVIOUSLY USED)

PLACED REMONUMENTATION BRASS TAG AND CAP #16937 ON IRON

Signed by E. Patrick O'Rourke  
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

2K 11147

RECORDED  
INDEXED  
FEB 28 1994  
REGISTER OF DEEDS

12/13/93 35696 REMO FEE 2.00  
 12/13/93 35696 DEED 14.00

FILE DO NOT MAIL

SECTION B (CONTINUED)

L.18569 P.329 DOES NOT DESCRIBE (1973)

S 29°09'E 37.42' P.K. NAIL IN U.P. (GONE)  
 S 19°W 46.13' "X" IN 2' SQ. CONCRETE SLAB (GONE)  
 N 15°25'W 34.75' P.K. NAIL IN U.P. (GONE)

L.18840 P.460 CONC. MON. IN BOX (1974)

N 80°E 130.89' P.K. NAIL IN DE POLE (GONE)  
 S 25°E 37.47' NAIL AND TAG IN POLE (GONE)  
 WEST 54.30' MON. BOX NORTHWEST CORNER SECTION 1 VAN BUREN TWP (MEAS. 54.32)  
 N15°W 34.01' P.K. NAIL IN POLE (GONE)

L.19990 P.617 CONC. MON. IN BOX (1977)

NE 52.94' NAIL WITH BRASS TAG IN NORTHWEST SIDE DE POLE (MEAS. 52.83)  
 SW 118.95' NAIL WITH BRASS TAG IN NORTH SIDE MBT POLE (GONE)  
 WEST 54.29' CONC. MON. IN BOX AT NORTHWEST CORNER SECTION 1 T3S, R8E (MEAS. 54.32)  
 NW 183.21' NAIL WITH BRASS TAG IN SOUTH SIDE DE POLE (GONE)