

For corners in **MAR 17 1998**

Liber-29739 Page-566.0
97327848LS 12/15/1997 08:46AM

WAYNE (County)	SECTION	Located in: TOWNSHIP OF CANTON (#07)	Corner Code # (#07)
1. Public Land Survey		T2S R 8E	L-1
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-13-97 *DP*

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, **WALTER J. ZBIKOWSKI**, in a field survey on **OCTOBER 8, 1997**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration.

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) THIS CORNER WAS NOT SET DURING THE ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819) AND NO MENTION IS MADE FOR THIS CORNER IN SAID ORIGINAL NOTES.
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
W.P.A. (1930's) MON, N-1 (#02)

WITNESSES:	NNE 69.25'	ED POLE (GONE)
	NE 79.25'	18" HICKORY (GONE)
	E 152.74'	MON. (MEASURED 152.81')
	SW 66.30'	24" MAPLE (GONE)

\$10.00 DEED
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #41828

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
FOUND 3/8" COPPERWELD PLAIN BRASS CAPPED REBAR IN ROAD BOX WITH LID (GOOD) IN THE CENTER OF JOY ROAD (A TWO LANE CONCRETE ROAD) JUST WEST OF INTERSTATE I-275 HIGHWAY OVERPASS.
DISTANCE TO K-1 MEASURED AS 2804.84'; W.P.A. (1930's) RECORD DISTANCE OF 2804.63';
DISTANCE TO M-1 TRAVERSED AS 2784.49'; W.P.A. (1930's) RECORD DISTANCE OF 2784.52';
W.P.A. (1970) IRON, N-1 (#02)

WITNESSES:	NNE 78.31'	D.E. POLE (GONE)
	NE 79.29'	18" HICKORY (GONE)
	E 152.70'	MON. (MEASURED 152.81')
	SE 48.83'	MBT POLE (GONE)
	SW 87.15'	CONC BLOCK BLDG (NE COR) (GONE)

L.18444 P.857, IRON ROD (1973) LCRC #238

WITNESSES:	S 55° E 48.92'	UTILITY POLE (PK NAIL IN POLE) (GONE)
	S 35° E 48.60'	SANITARY MANHOLE COVER
	S 85° W 170.67'	UTILITY POLE (GONE)



(CONTINUED ON BACK)

\$4.00 REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
L-1, SECTION CORNER NORTH OF 1, T.2S., R.8E A 3/8" COPPERWELD REBAR IN A ROAD BOX WITH LID (GOOD) AT THE CENTER OF JOY ROAD (A TWO LANE CONCRETE ROAD) JUST WEST OF INTERSTATE I-275 HIGHWAY OVERPASS AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. THIS CORNER IS NOT COMMON WITH L-13, SECTION CORNER SOUTH OF 36, T.1S., R.8E.

WITNESSES:	N 18°34' E 79.58'	SET NAIL/WCR BRASS DISK ON EAST SIDE OF POWER POLE
	S 88°42' E 152.81'	FOUND 3/8" COPPERWELD REBAR IN ROAD BOX (SECTION CORNER L13, SOUTH OF 36, T.1S., R.8E.) (SUPRA)
	S 44°09' E 164.39'	FOUND NNW CORNER OF BRICK APARTMENT BUILDING #8699-5 (SUPRA)
	S 00°30' W 69.33'	FOUND NORTHWEST CORNER OF 3" SQUARE FENCE ANCHOR POST (SUPRA)
	N 57°41' W 128.09'	SET NAIL/WCR BRASS DISK ON SOUTHWEST SIDE OF UTILITY POLE

PLACED A REMONUMENTATION BRASS DISK STAMPED WITH LLS #21586 AROUND EXISTING 3/8" COPPERWELD REBAR L-1.

Signed by Walter J. Zbikowski Date DEC. 9, 1997
Surveyor's Michigan License No. 21586

DP
R-LCR-10-4R-2PG-U

L.21297 P. 922, SET COPPERWELD ROD IN MONUMENT BOX (1981) LCRC #783

WITNESSES:	N 25° W	75.92'	CENTER OF (FOUND CHISELED "X" W/S) FENCE ANCHOR POST (MEASURED 75.83)
	N 13° E	78.21'	NAIL AND MDOT TAG IN W FACE OF UTILITY POLE (GONE)
	S 47° E	164.38'	NW CORNER APARTMENT BLDG. (MEASURED 164.39')
	S 03° E	69.38'	NW CORNER 3" SQUARE FENCE ANCHOR POST (MEASURED 69.33')
	N 88° E	152.64'	COPPERWELD ROD IN MONUMENT BOX (S 1/4 COR SEC 36) (MEASURED 152.81')

SURVEY &
REMONUMENTATION

MAR 17 1998

SECTION

FILE DO NOT MAIL