

SURVEY & REMONUMENTATION

RC 1493

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County) Located in: TOWNSHIP OF CANTON #07 Corner Code # L-3
1. Public Land Survey T 2S R 8E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

L127797PA634

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, E. PATRICK O'ROURKE, in a field survey on OCT. 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is present at row 3, column L.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1819) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: ASH 14 N 55 E 4 (2.64 R) (GONE)
DO 13 S 4-1/2 E 5 (3.30 R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:01 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE AT SOUTH END OF TREE ROW
DISTANCE TO K-3 TRAVERSED AS 2738.31'; RECORD WPA (1930) DISTANCES AS 2737.73' AND 2738.40'
DISTANCE TO M-3 TRAVERSED AS 2750.95'; RECORD WPA (1930) DISTANCES AS 2750.48' AND 2748.38'
L.C.R.C. # 847 L.22177 P.495 3/4" IRON PIPE SOUTH 1/4 SECTION 1
N 76° E 12.96' NAIL IN CAP #19837 (GONE)
N 35° E 7.91' NAIL IN WASHER IN 12" OAK (GONE)
N 76° W 19.75' PK NAIL IN 12" AND 6" DOUBLE OAK (GONE)

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SOUTH 1/4 CORNER SECTION 1, NORTH 1/4 CORNER SECTION 12 T.2S, R.8E
SET CONCRETE MONUMENT WITH 3/8" RE-ROD AT SOUTH END TREE ROW, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.
WITNESSES: N 6°10' E 7.82' NAIL/SHINER SOUTHEAST SIDE 14" MAPLE (W.C.R. TAG)
N 55° E 19.13' NAIL/SHINER NORTH SIDE TWIN 14" 16" OAK (W.C.R. TAG)
N 89° E 26.95' NAIL/SHINER NORTH SIDE 14" OAK (W.C.R. TAG)
N 89° W 19.40' NAIL/SHINER EAST SIDE TWIN 14" AND 10" MAPLE (W.C.R. TAG)

PLACED A REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD PIPE.

Signed by [Signature] Date 12-27-94
E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

L127797PA635

SECTION A (CONTINUED)

WPA (1930s) IRON SET N 12 #28

WITNESSES: NE 58.02 5" OAK (GONE)
SW 27.3 12" OAK (GONE)

MDOT (1976) STATE PROJECT #82293 - 3/4" IRON PIPE SOUTH 1/4 SECTION 1

WITNESSES: N 5° E 23.36 11" OAK (GONE)
N 39° E 57.90 10" OAK (GONE)
N 88° E 26.78 21" TWIN OAK (GONE)