

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1495**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LI27797PA638**

For corners in

WAYNE (County)	Located In: TOWNSHIP OF CANTON	Corner Code -#
1. Public Land Survey	T 2S R 8E	L-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
**ACT 345, P.A. 1990**

APPROVED ON: 12-7-94 *[Signature]*

**WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE**

**Register of Deeds Stamp & File Number**

**RC 1495**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

\$ 16.00 MISCELLANEOUS RECORDING  
 27 DEC 94 11:02 A.M. RECEIPT# 48A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)  
 G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.  
 WITNESSES: SUGAR 5 N 19 E 5 (3.30' R) (GONE)  
 ELM 8 S 27 W 16 (10.56' R) (GONE)  
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

(CONTINUED ON BACK)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/8" RE-ROD IN MONUMENT BOX.  
 DISTANCE TO M-7 MEASURED AS 2697.20'; RECORD WPA (1930) DISTANCES OF 2697.08' AND 2697.29'  
 DISTANCE TO K-7 MEASURED AS 2715.80'; RECORD WPA (1930) DISTANCES OF 2714.88' AND 2715.19'  
 L.18603 P.255 1/2" IRON IN MONUMENT BOX (1973) ACT 74 FORM  
 N 42°E 49.05' NAIL IN FLASHER (WCRC) SOUTHEAST FACE UTILITY POLE (GONE)  
 S 38°W 45.06' CHISLED "X" SOUTHEAST RIM OF SANITARY MANHOLE (MEASURED 46.75)  
 N 60°W 90.82' NAIL IN FLASHER (WCRC) SOUTHWEST FACE OF UTILITY POLE (MEASURED 90.80)  
 L.18650 P.765-766 FOUND ROD IN HANDHOLE (1973) ACT 74 FORM  
 N 45°E 49.05' NAIL WITH CAP IN DETROIT EDISON POLE SOUTHEAST SIDE (GONE)  
 S 20°E 50.60' NORTH FACE OF STOP SIGN POSTS (GONE)  
 SOUTH 15.00 PK NAIL (GONE)  
 N 50°W 76.56' TOP OF NUT ON HYDRANT (MEASURED 76.57)

(CONTINUED ON BACK)



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-7 SOUTH 1/4 CORNER SECTION 13, NORTH 1/4 CORNER SECTION 24 T.2S, R.8E  
 FOUND 3/8" RE ROD IN MONUMENT BOX AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 WITNESSES: N 30° E 63.20 NAIL IN SHINER SOUTHEAST SIDE DETROIT EDISON POLE (PREVIOUSLY USED) (W.C.R.C. TAG)  
 S 30° E 60.48 NAIL IN SHINER NORTHEAST SIDE DETROIT EDISON POLE (PREVIOUSLY USED) (W.C.R.C. TAG)  
 S 38° W 46.75 CHISLED "X" SOUTHEAST RIM OF SANITARY MANHOLE (PREVIOUSLY USED)  
 N 51° W 76.57 CENTERLINE TOP BOLT HYDRANT (PREVIOUSLY USED)

PLACED A REMONUMENTATION BRASS TAB AND CAP #16937 ON RE-ROD

Signed by *[Signature]*  
 E. PATRICK O'ROURKE  
 Surveyor's Michigan License No. 16937

Date 12-27-94

2 R  
 14 D  
 MISC.

L127797PA639

SECTION A (CONTINUED)

WPA (1930) IRON N 24 #80

WITNESSES: NE 48.23 TELEPHONE POLE (GONE)  
SE 48.57 POLE (GONE)  
SE 75.45 18" WILD CHERRY (GONE)  
SW 39.60 TELEPHONE POLE (GONE)

W.C.R.C. (1980) 1/2" RE ROD IN MONUMENT BOX #80

WITNESSES: N 33° E 63.20 WHITE CAPPED PK NAIL SOUTHEAST SIDE DETROIT EDISON POLE (MEASURED 63.20)  
S 33° E 60.48 WHITE CAPPED PK NAIL NORTHEAST SIDE DETROIT EDISON POLE (MEASURED 60.48)  
S 39° W 62.07 WHITE CAPPED PK NAIL SOUTHEAST SIDE DETROIT EDISON POLE (GONE)  
N 51° W 76.57 CENTERLINE TOP BOLT FIRE HYDRANT (MEASURED 76.57)

SECTION B (CONTINUED)

L.18650 P.771-776 (1973) CS

SAME WITNESSES AS L.18650 P.765-766, ACT 74 FORM