

**SURVEY &
REMONUMENTATION**

RC 1496

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
WAYNE
(County)

Located In: TOWNSHIP OF CANTON #07
Corner Code #

L127797PA640

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- | | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 2S | R | 8E | L-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, E. PATRICK O'ROURKE, in a field survey on OCTOBER 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
 WITNESSES: ASH 24 S 84 E 20 (13.20' R) (GONE)
 IRON'D 5 S 47 W 8 (5.28' R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:02 A.M. RECEIPT# 48A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

(CONTINUED ON BACK)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 3/8" RE-ROD IN CONCRETE MONUMENT IN ROAD BOX, 6" BELOW RIM.
 DISTANCE TO K-9 MEASURED AS 2707.84'; RECORD WPA (1930) DISTANCES AS 2706.58' AND 2705.54'
 DISTANCE TO M-9 MEASURED AS 2707.39'; RECORD WPA (1930) DISTANCES AS 2707.51' AND 2706.65'
 L.20402 P.906 FOUND 1/2" IRON PIPE (1979) ACT 74 FORM
 N 30° E 66.47 PK NAIL WEST SIDE GUY POLE (GONE)
 S 35° E 40.20 PK NAIL SOUTHWEST SIDE DETROIT EDISON POLE (GONE)
 S 40° W 39.59 PK NAIL NORTHWEST SIDE MICHIGAN BELL TELEPHONE POLE (GONE)
 SW S 0.40 AND W 0.20 1/2" RE-ROD (GONE)

(CONTINUED ON BACK)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-9 NORTH 1/4 CORNER SECTION 25; SOUTH 1/4 CORNER SECTION 24, T.2S, R.8E
 FOUND 3/8" RE ROD IN CONCRETE MONUMENT IN ROAD BOX, 6" BELOW RIM, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N 27°26' E 69.26 NAIL WITH SHINER IN WEST SIDE GUY POLE (PREVIOUSLY USED) (W.C.R.C. TAGS)
 S 36°03' E 62.89 NAIL WITH SHINER IN NORTHEAST SIDE UTILITY POLE (PREVIOUSLY USED) (" ")
 S 55°56' W 54.77 NAIL WITH SHINER IN NORTHWEST SIDE UTILITY POLE (PREVIOUSLY USED) (" ")
 N 15°18' W 103.95 NAIL WITH SHINER IN SOUTHWEST SIDE UTILITY POLE (PREVIOUSLY USED) (" ")

PLACED A REMONUMENTATION TAG AND CAP #16937 ON RE-ROD.



Signed by E. Patrick O'Rourke
 Surveyor's Michigan License No. 16937

Date 12-27-94

LI27797PA641

SECTION A (CONTINUED)

WPA (1930) IRON N 25 #106

WITNESSES: SE 40.80' TELEPHONE POLE (GONE)
SSW 70.80' 8" CATALPA (GONE)
SW 55.98' 12" CATALPA (GONE)
NW 36.05' TELEPHONE POLE (GONE)

SECTION B: (CONTINUED)

L.25576 P.473 MONUMENT IN HANDHOLE (1992) ACT 74 FORM

NE 69.28' NAIL WITH CAP IN SIGNAL POLE (MEASURED 69.26)
SE 62.96' NAIL WITH CAP IN DETROIT EDISON POLE (MEASURED 62.87)
SW 54.85' NAIL WITH CAP IN DETROIT EDISON POLE (MEASURED 54.77)
NW 103.98' PK NAIL IN DETROIT EDISON POLE (MEASURED 103.95)

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS