

**SURVEY &
REMONUMENTATION**

APR 25 1995

RC 1497

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

WAYNE (County)	Located In: TOWNSHIP OF CANTON #07	Corner Code #
1. Public Land Survey	T 2S R 8E	L-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L127797PA642

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1497

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: BEECH 21 N 85-1/2 W 14 (9.24' R) (GONE)
DO 10 N 73 E 20 (13.20' R) (GONE)

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:02 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN ROAD BOX AT CENTERLINE CONCRETE PAVEMENT.
DISTANCE TO K-11 MEASURED AS 2671.67'; RECORD WPA (1930) DISTANCES AS 2671.21' AND 2671.66'
DISTANCE TO M-11 MEASURED AS 2675.93'; RECORD WPA (1930) DISTANCES AS 2675.76' AND 2675.94'
L.20402 P.902 FOUND 1/2" IRON PIPE S-25
N 40° E 47.13 PK NAIL SOUTHEAST SIDE DETROIT EDISON POLE (MEASURED 47.43')
S 85° E 29.70 PK NAIL SOUTH SIDE DETROIT EDISON GUY POLE (GONE)
N 80° W 72.68 PK NAIL SOUTH SIDE 20" TREE (GONE)
N 45° W 89.14 PK NAIL SOUTH SIDE DETROIT EDISON POLE (GONE)



(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 SOUTH 1/4 CORNER SECTION 25, NORTH 1/4 CORNER SECTION 36, T.2S, R.8E
FOUND 3/4" IRON PIPE IN ROAD BOX AT CENTERLINE CONCRETE PAVEMENT AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 38°13' E 58.20' CENTERLINE TOP OF FIRE HYDRANT (PREVIOUSLY USED)
N 45°21' E 47.43' NAIL/SHINER SOUTHEAST SIDE UTILITY POLE (PREVIOUSLY USED) (W.C.R. TAG)
S 72°34' W 47.02' NAIL/SHINER SOUTH SIDE 6" MAPLE (W.C.R. TAG)
N 41°45' W 80.25' NAIL/SHINER NORTHEAST SIDE UTILITY POLE (W.C.R. TAG)

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON 3/4" IRON L-11

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

*L.R.
12-27-94
MTC*

L127797PA643

SECTION A (CONTINUED)

WPA (1930) CROSS IN STONE N 36 #132

WITNESSES: N 83.40 CENTERLINE SOUTH PAVEMENT (RELOCATED)
NE 61.54 TELEPHONE POLE (GONE)
SE 24.95 12" APPLE (GONE)
NW 27.53 EDISON POLE (GONE)

WCRC (1970) IRON N 36 #132

WITNESSES: N 83.40 CENTERLINE SOUTH PAVEMENT (MEASURED 83.40+/-)
NE 61.79 MICHIGAN BELL TELEPHONE POLE (GONE)
SE 29.22 MICHIGAN BELL TELEPHONE POLE (GONE)
SW 29.28 DETROIT EDISON POLE (GONE)

SECTION B (CONTINUED)

L.20536 P.278 FOUND 3/4" PIPE N 36

EAST 29.15 TELEPHONE POLE (GONE)
N 57° E 46.80 POWER POLE (GONE)
N 55° E 58.48 FIRE HYDRANT (MEASURED 58.20')
N 80° W 73.06 14" POPLAR (GONE)
N 40° W 89.38 TELEPHONE POLE (GONE)

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS