

SURVEY & REMONUMENTATION

RC 1498

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located In: TOWNSHIP OF CANTON	Corner Code # L-13
1. Public Land Survey	T <u>2S</u> R <u>8E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

L127797PA644

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-7-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1498

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
 G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
 WITNESSES: ASH 24 S 57 W 28 (18.48 R)(GONE)
 SUGAR 12 N 9 E 27 (17.82 R)(GONE)
 RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD IN MONUMENT BOX IN CENTERLINE OF ASPHALT ROAD.
 DISTANCE TO K-13 MEASURED AS 2656.19'; RECORD WPA (1930) DISTANCE OF 2655.61'
 DISTANCE TO M-13 MEASURED AS 2638.78'; RECORD WPA (1930) DISTANCE OF 2638.42'
 L.18746 P.842 FOUND 1/2" ROD IN MONUMENT BOX (1974)
 N 45° W 41.82 UTILITY POLE (MEASURED 41.16)
 S 50° W 59.89 UTILITY POLE (GONE)
 N 45° E 43.15 GAS MARKER (GONE)
 S 50° E 50.21 30" ELM (GONE)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 SOUTH 1/4 CORNER SECTION 36 T.2S, R.8E
 FOUND 1/2" ROD IN MONUMENT BOX IN CENTERLINE ASPHALT ROAD AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N 40° E 75.39 CENTERLINE TOP OF HYDRANT
 N 48° E 71.48 NAIL IN CAP SOUTHEAST SIDE 16" TREE
 S 45° W 44.80 NAIL IN CAP CENTERLINE TOP GUARDRAIL POST
 S 85° W 35.18 IRON IN MONUMENT BOX (PREVIOUSLY USED)
 N 45° W 41.16 FLASH IN EAST SIDE UTILITY POLE

\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:02 A.M. RECEIPT# 400
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

PLACED REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD

Signed by

E. Patrick O'Rourke

Date

12-27-94

Surveyor's Michigan License No. E. PATRICK O'ROURKE

16937

*1 R
 14-D
 MISC*

LI27797PA645

SECTION A (CONTINUED)

W.P.A. (1930s) CROSS S 36 #158

WITNESSES: NE 43.53 CONCRETE ROAD SIGN POST (GONE)
SE 50.40 26" ELM (GONE)
SW 60.13 POLE (GONE)
W 35.18 IRON (MEASURED 35.18)
NW 42.16 EDISON POLE (MEASURED 41.82)

W.C.R.C. (1970s) MONUMENT IN BOX S 36 #158

WITNESSES: NE 42.98 SOUTHWEST CORNER ROAD SIGN BASE (GONE)
SW 62.85 DETROIT EDISON POLE (GONE)
SW 59.88 MICHIGAN BELL TELEPHONE POLE (GONE)
W 35.18 IRON (MEASURED 35.18)
NW 41.80 DETROIT EDISON (MEASURED 41.82)