

**SURVEY &  
REMONUMENTATION**

**RC 1499**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>WAYNE</u> (County)	Located In: TOWNSHIP OF CANTON 407	Corner Code # M-1
1. Public Land Survey	T 2S R8E	M-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**LI27797PA646**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-7-94  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

**RC 1499**

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)  
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES  
WITNESSES: R.O. 10 N 45 W 5 (3.30 R) (GONE)  
ASH 16 S 37 E 34 (22.44 R) (GONE)  
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

\$ 16.00 MISCELLANEOUS RECORDING  
27 DEC 94 11:02 A.M. RECEIPT# 48A  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

(CONTINUED ON BACK)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/8" RE-ROD IN CONCRETE MONUMENT IN ROAD BOX ON CENTERLINE OF JOY ROAD PAVEMENT.  
DISTANCE TO L-1 MEASURED AS 2784.49'; RECORD WPA (1930) DISTANCE AS 2784.52'  
DISTANCE TO M-2 TRAVERSED AS 2655.58'; RECORD WPA (1930) DISTANCE AS 2655.42'  
NO L.C.R.C. RECORDED AT WAYNE COUNTY REGISTER OF DEEDS  
WADE-TRIM TIES 1980 (NOT RECORDED) CONCRETE MONUMENT IN MONUMENT BOX  
NE 44.00' CENTERLINE 3/4" IRON BAR IN CONCRETE (WCRC BM #60-60) (GONE)  
SE 69.40' PK NAIL NORTH SIDE 10" ELM (GONE)  
SSE 48.80' PK NAIL EAST SIDE 14" ELM (GONE)  
SSW 52.25' PK NAIL WEST SIDE 6" ELM (GONE)

(CONTINUED ON BACK)



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-1 NORTHEAST CORNER SECTION 1, T.2S., R.8E., FOUND 3/8" RE-ROD IN CONCRETE MONUMENT IN ROAD BOX ON THE CENTERLINE OF JOY ROAD PAVEMENT, AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
WITNESSES: N 44°42' E 86.00 NAIL/SHINER SOUTHWEST SIDE DETROIT EDISON POLE (WCR TAG)  
S 34°39' E 48.94 NAIL/SHINER EAST SIDE 18" MAPLE (WCR TAG)  
S 64°10' W 104.04 TOP CENTER FIRE HYDRANT  
N 43°20' W 82.56 NAIL/SHINER TOP GUARD RAIL POST WESTERLY MOST POST (WCR TAG)  
N 20°42' E 64.93 NAIL/SHINER TOP GUARD RAIL POST 4TH POST WEST OF EAST END (WCR TAG)

PLACED A REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD.

Signed by E. Patrick O'Rourke  
Surveyor's Michigan License No. 16937

Date 12-27-94

LI27797PA647

SECTION A (CONTINUED)

WPA (1930) MONUMENT

WITNESSES:	NORTH	33.00	MONUMENT (GONE)
	NNE	76.35	6" MAPLE (GONE)
	NE	36.05	2" ELM (GONE)
	SE	41.59	MANHOLE COVER (GONE)
	SOUTH	33.05	MONUMENT (GONE)
	NW	46.48	14" ELM (GONE)

SECTION B (CONTINUED)

VERIFICATION OF NORTHEAST CORNER SECTION 1 T.2S., R.8E., BY ANGLES AND DISTANCES TO MONUMENT FOUND IN HOLIDAY PARK SUBDIVISION NO. 3. RECORDED IN L.88 P.69-70.

MEAS. TO MONUMENT AT NORTHWEST CORNER HANNAN (UNIMPROVED) AND BART AVENUE 733.38 SOUTH AND 59.79' WEST OF NORTHEAST CORNER SECTION 1, RECORDED AS 733.58' SOUTH AND 60' WEST OF NORTHEAST CORNER SECTION 1.

MEAS. TO MONUMENT AT SOUTHEAST SIDE SUBDIVISION CORNER OF HOLIDAY PARK SUBDIVISION NO. 3 AS 2287.39' SOUTH AND 60.98' WEST OF NORTHEAST CORNER SECTION 1, RECORDED AS 2286.568' SOUTH AND 60' WEST OF NORTHEAST CORNER SECTION 1 (MONUMENT BENT).