

FEB 28 1994

LI 27033 PA 895

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE (County)

Located In: TWP. OF CANTON Corner Code #

Table with 3 columns: Survey Type, T/R coordinates, and Corner Code. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990 APPROVED ON: 12-10-93 [Signature] WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

RC 1303

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 6-36.

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT IS NOT STATED IN NOTES

WITNESSES: BEECH 6 S5E 2 (1.32') (GONE) BEECH 8 N5W 2 (1.32') (GONE)

WPA 1930's - SET IRON - #27

WITNESSES: NORTH 64.41' 16" ELM (GONE) ESE 30.11' 10" MAPLE (GONE) SSE 20.93' TWIN 8" CHERRY (GONE) NW 61.10' 18" BEECH (GONE)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO M-2 CORNER SECTION 1 MEASURES AS 2643.43'; RECORDED WPA 1930 DISTANCE 2643.62'

L.18256 P.856 FOUND CONCRETE MONUMENT (1972)

SE 30.23' 18" MAPLE (GONE) SE 21.22' TWIN 18" CHERRY (GONE) NW 16.61' 12" POPLAR (GONE)

ONLY SUBSEQUENT L.C.R.C. AT WAYNE COUNTY REGISTER OF DEEDS

93 DEC 13 PM 5:29 FOREST COUNTY REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 SOUTHEAST CORNER SECTION 1 T2S, R8E FOUND CONCRETE MONUMENT (IN WOODS) AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: S 76°01'E 29.67' P.K. NAIL IN TAG SOUTHWEST SIDE 30" OAK TREE S 16°20'E 21.00' P.K. NAIL IN TAG WEST SIDE 12" OAK TREE N 71°22'W 16.49' P.K. NAIL IN TAG SOUTH SIDE 16" OAK TREE N 17°45'W 20.00' WAYNE COUNTY WITNESS TAG EAST SIDE 10" OAK TREE

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE MONUMENT M-3

Signed by [Signature] E. PATRICK O'ROURKE Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993

[Handwritten initials]