

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE COMMISSION Located In: Corner Code #
TWP. OF CANTON

- 1. Public Land Survey T 2S R 8E M-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1304

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES

WITNESSES: IRONW'D 6 S22W 9 (5.94') (GONE)
IRONW'D 5 N47E 9 (5.94') (GONE)

WPA 1930's IRON #131

WITNESSES: NORTH 151.80' STONE (GONE) ENE 26.45' EDISON POLE (GONE)
NNE 97.15' 10" ELM (GONE) NW 85.40' 10" MULBERRY (GONE)
NE 74.64' 10" ELM (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO EAST 1/4 CORNER SECTION 25 MEASURED AS 2652.27'; RECORDED WPA 1930 DISTANCE 2652.85'
DISTANCE TO EAST 1/4 CORNER SECTION 36 MEASURED AS 2659.26'; RECORDED WPA 1930 DISTANCE 2658.89'
L.20402 P.905 FOUND CONCRETE MONUMENT IN BOX (1979)
SE 22.42' CENTERLINE BASE ROAD SIGN (GONE)
SE 130.60' NAIL WEST SIDE MULTIPLE TRUNK HICKORY TREE (GONE)
SW 193.80' P.K. NAIL NORTHWEST SIDE MBT POLE (GONE)
NW 29.93' CONCRETE MONUMENT (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 FOUND 1/2" IRON PIPE IN MON. BOX AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: S 86°37'E 115.93' NORTHWEST CORNER BUILDING #39390 MICHIGAN AVENUE
S 14°23'E 91.99' "X" CHISELED IN WEST RIM SANITARY MANHOLE
S 57°07'W 105.99' WAYNE COUNTY TAG AND NAIL NORTH SIDE TWIN 8" ELM
N 19°36'W 72.69' "X" CHISELED IN TOP OF SOUTH END 12" CONCRETE CULVERT

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE FOUND 1/2" IRON PIPE M-11

Signed by [Signature]
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993



Handwritten initials: 2R 11K7

Vertical stamp: FOREST COUNTY REGISTER OF DEEDS

Vertical stamp: 23 DEC 13 PM 5: 29