

SURVEY & REMONUMENTATION

APR 25 1995

RC 1505

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA658

For corners in

WAYNE (County)	Located In: TOWNSHIP OF CANTON	Corner Code #
1. Public Land Survey	T 2S R 8E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 12-7-94
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1819)
 G.L.O. (1819) DESCRIPTION OF CORNER NOT STATED IN NOTES
 WITNESSES: BEECH 16 S 12 E 23 (15.18' R) (GONE)
 BEECH 15 N 4 W 20 (13.20' R) (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION
 WPA (1930's) - IRON - #156

(CONTINUED ON BACK)

\$ 16.00 MISCELLANEOUS RECORDING
 27 DEC 94 11:03 A.M. RECEIPT# 48A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT IN HANDHOLE ROAD BOX IN CENTERLINE OF ASPHALT PAVEMENT.
 DISTANCE TO M-13 MEASURED AS 2642.33'; RECORD W.P.A. (1930) DISTANCE AS 2642.00'
 DISTANCE TO M-11 MEASURED AS 2659.26'; RECORD W.P.A. (1930) DISTANCE AS 2658.89'
 L.18638 P.330 FOUND MONUMENT IN BOX
 25.30 EAST 10" ELM (GONE)
 105.40 SE NW CORNER HOUSE (GONE)
 43.10 W 36" ELM (GONE)
 93.20 NE 12" ELM (GONE)

NO OTHER L.C.R.C. OR CS RECORDED



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 E 1/4 CORNER SECTION 36
 FOUND MONUMENT IN HANDHOLE ROAD BOX CENTERLINE OF ASPHALT PAVEMENT AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 WITNESSES: N 169.15 MONUMENT IN ROAD BOX, E 1/4 CORNER SECTION 36, T.2S, R.9E
 N 31°47' E 77.32 NAIL IN TAG WEST SIDE OF 12" MAPLE
 S 21°34' E 121.48 CENTERLINE TOP HYDRANT
 S 14°55' W 82.57 NAIL IN TAG NORTH END GUARDRAIL POST
 N 27°19' W 105.63 NAIL IN TAG NORTHEAST SIDE POLE

PLACED REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD

Signed by E. Patrick O'Rourke
 Surveyor's Michigan License No. 16937

Date 12-27-94

2K
 14-P
 MISC

0001 111

LI27797PA659

SECTION A (CONTINUED)

WITNESSES: N 169.14 IRON (MEASURED 169.15)
NE 93.20 12" ELM (GONE)
SE 62.20 6" ELM (GONE)
W 43.07 36" ELM (GONE)

W.C.R.C. (1977) NOT RECORDED

N 169.14 IRON (MEASURED 169.15)
NE 77.78 10" NOW 12" MAPLE (MEASURED 77.32)
SE 105.45 NW CORNER HOUSE (GONE)
SE 89.05 15" MAPLE (GONE)
SW 42.95 MICHIGAN BELL TELEPHONE POLE (GONE)
SW 125.00 TANGENT SOUTH SIDE GATE POST (GONE)
NW 92.30 14" ELM (GONE)