

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

WAYNE (County) Located In: TWP. OF CANTON Corner Code #
1. Public Land Survey T 2S R 8E M-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1305

I, E. PATRICK O'ROURKE, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1815-1816) DESCRIPTION OF MONUMENT NOT STATED IN NOTES

WITNESSES: ASH 24 S57W 28 (18.48') (GONE)
SUGAR 12 N9E 29 (19.14') (GONE)

W.P.A. 1930's IRON #157

WITNESSES: N 189.72' MON (MEAS. 189.72') SW 80.08' TELEPHONE POLE (GONE)
NE 58.30' ED POLE (GONE) WNW 64.69' MON. (GONE)
SE 41.06' TELEPHONE POLE (GONE) NW 70.97' TELEPHONE POLE (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO EAST 1/4 CORNER SECTION 36 MEASURED AS 2642.33'; RECORDED WPA 1930 DISTANCE AS 2642.00'
DISTANCE TO SOUTH 1/4 CORNER SECTION 36 MEASURED AS 2638.78'; RECORDED WPA 1930 DISTANCE AS 2638.42'
L.18746 P.844 FOUND 1/2" IRON ROD IN MON. BOX (1974)
N 40°E 56.00' UTILITY POLE (GONE)
S 40°E 43.22' UTILITY POLE (GONE)
S 55°W 36.18' UTILITY POLE (GONE)
N 30°W 92.60' UTILITY POLE (GONE)

L.20939 P.50
NO TIES LISTED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 FOUND 3/8" REROD IN CONCRETE MON. IN MON. BOX AND IT IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

WITNESSES: N 02°14'E 189.72' 1/2" IRON IN MON. BOX (PREVIOUSLY USED 1930's)
N 37°16'E 78.41' NAIL AND SHINER SOUTHEAST SIDE UTILITY POLE
S 55°01'E 48.91' GW #5469 NAIL AND SHINER NORTHEAST SIDE UTILITY POLE
S 53°42'W 54.31' NAIL AND SHINER SOUTHEAST SIDE UTILITY POLE
N 27°23'W 88.39' WAYNE COUNTY NAIL AND SHINER SOUTHWEST SIDE 12" ELM

PLACED A REMONUMENTATION BRASS DISC AND CAP #16937 ON ABOVE 3/8" REROD M-13

Signed by [Signature]
E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

Date DECEMBER 7, 1993



Handwritten initials: 2R 11K 7