

RC 1500

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA648

For corners in

WAYNE (County)

Located In: TOWNSHIP OF CANTON #07

Corner Code #

- 1. Public Land Survey T 2S R8E M-2\* COMMON COR. TO: A-2 (WESTLAND)
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: BEECH 16 S 52 E 8 (5.28' R) (GONE)
IRONWD 6 N 43 W 24 (15.84' R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT WITH 3/8" RE-ROD.
DISTANCE TO M-1 TRAVERSED AS 2655.58'; RECORD WPA (1930) DISTANCE AS 2655.42'
DISTANCE TO M-3 TRAVERSED AS 2642.74'; RECORD WPA (1930) DISTANCE AS 2643.62'
WADE-TRIM TIES 1980 (NOT RECORDED) CONCRETE MONUMENT
SE 75.20 PK NAIL WEST SIDE 6" COTTONWOOD (GONE)
SW 40.37 PK NAIL IN REF CAP NORTHWEST SIDE MICHIGAN BELL TELEPHONE POLE (GONE)
NW 43.60 PK NAIL NORTH SIDE TWIN 18" MAPLE (GONE)
NNW 14.15 PK NAIL WEST SIDE 14" ELM (MEAS. 14.04)

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner and faithful perpetuation of the position of the original corner.
M-2 EAST 1/4 CORNER SECTION 1 T.2S., R.8E. FOUND CONCRETE MONUMENT AND IT IS ACCEPTED AS A CAREFUL RECORD
WITNESSES: S 50°30' E 69.30' NAIL/SHINER NORTHEAST SIDE UTILITY POLE (WCR TAG)
S 44°10' W 39.65' CENTERLINE TOP FIRE HYDRANT
S 89°30' W 48.73' NAIL/SHINER NORTH SIDE 6" MAPLE (WCR TAG)
N 2°13' W 14.04' PK NAIL WEST SIDE 18" ELM (PREVIOUSLY USED)

PLACED A REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD.

Grid table with columns A-L and rows 2-13. Contains numbers 1-36.



Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

LI27797PA649

SECTION A (CONTINUED)

WPA (1930) IRON #26

WITNESSES: NORTH 13.82 F. POST (MEAS. 11.90)  
NE 118.00 12" POPLAR (GONE)  
NE 143.85 18" MAPLE (GONE)  
SE 94.50 HUB (GONE)  
WEST 49.23 4" CHERRY (GONE)  
NW 54.42 14" BEECH (GONE)

SECTION B (CONTINUED)

VERIFICATION OF EAST 1/4 CORNER SECTION 1 T.2S., R.8E, BY MEASUREMENTS TO MONUMENTS FOUND IN HOLIDAY PARK SUBDIVISION NO. 2, L.88, P. 82 & 83

MEASURE TO SOUTHEAST SUBDIVISION CORNER AT HANNAN AND KOPPERNICK ROAD TO EAST AS DUE WEST 59.93'  
RECORDED AS DUE WEST 60.00'

MEASURE TO NORTHEAST SUBDIVISION CORNER AT IMPROVED HANNAN STREET AT 368.60' NORTH AND 61.00' WEST  
RECORDED AS 369.08' NORTH AND 60.00' WEST (MONUMENT BENT)