

RC 1501

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA650

For corners in

WAYNE <small>(County)</small>	Located In: TOWNSHIP OF CANTON	Corner Code #
1. Public Land Survey	T 2S R 8E	M-4 COMMON
	T R	CORNER TO
	T 2S R 9E	✓ (A-4) (WESTLAND)
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *DPJ*

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES
WITNESSES: ASH 16 EAST 11 (7.26' R) (GONE)
IRONWOOD 4 S 63 W 4 (2.64' R) (GONE)
RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

\$ 16.00 MISCELLANEOUS RECORDING
27 DEC 94 11:03 A.M. RECEIPT# 48A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DISTANCE TO M-3 TRAVERSED AS 2641.98'; RECORD WPA (1930s) DISTANCE OF 2642.58'
DISTANCE TO M-5 TRAVERSED AS 2634.17'; RECORD WPA (1930s) DISTANCE OF 2634.02'
L.C.R.C. #365 L.18960 P.699 FOUND 1" IRON PIPE
NORTH 9.88' FENCE POST (GONE)
SOUTH 3.45' FENCE POST (GONE)
N 40°W 40.00' CORNER OF BLOCK BARN (GONE)
N 10°W 36.90' CORNER OF BARN (GONE)

NO OTHER L.C.R.C. ON RECORD AT WAYNE COUNTY REGISTER OF DEEDS



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST 1/4 CORNER SECTION 12 T.2S, R.8E
FOUND 3/8" RE ROD ON WOOD FENCE LINE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER
WITNESSES: N 2°30' E 67.83' CENTERLINE TOP OF FIRE HYDRANT
N 88°30'E 67.72' NORTHWEST CORNER METAL BASE ON TOP OF CONCRETE BASE OF LIGHT POLE
S 89°30'E 40.95' SOUTHWEST CORNER CATCH BASIN RIM
S 1°30' E 78.82' NAIL/FLASHER EAST SIDE UTILITY POLE

PLACED A REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD.

Signed by *E. Patrick O'Rourke*
E. PATRICK O'ROURKE
Surveyor's Michigan License No. 16937

Date 12-27-94

2K
14D
misc

SECTION A (CONTINUED)

LI27797PA651

WPA (1930s) SET IRON E-12 #52

WITNESSES: NORTH 99.35' 14" CHERRY (GONE)
SW 75.00' 30" ELM STUMP (GONE)
WEST 39.12' 6" MAPLE (GONE)
NW 102.08' 12" TWIN ELM (GONE)