

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127797PA654

For corners in

WAYNE (County) Located In: TOWNSHIP OF CANTON #07 Corner Code # M-6 \* COMMON CORNER TO A-C (WESTLAND)
1. Public Land Survey T 25 R 8E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-7-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1503

- 4. Lot No. , Recorded Plat
5. Private Claims

I, E. PATRICK O'ROURKE, in a field survey on NOVEMBER 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY BY T. WAMPLER, D.S. (1815-1819)
G.L.O. (1816) DESCRIPTION OF CORNER NOT STATED IN NOTES.
WITNESSES: ELM 50 S 14 E 18 (11.88 R) (GONE)
GUM 24 N 22 W 23 (15.18 R) (GONE)

RESURVEY AT THE DIRECTION OF ALBERT E. CHAMPNEY, DIRECTOR OF WAYNE COUNTY BUREAU OF TAXATION

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN MODERATELY WOODED AREA.
DISTANCE TO M-5 TRAVERSED AS 2645.28'; RECORD WPA (1930) DISTANCE AS 2646.90'
DISTANCE TO M-7 TRAVERSED AS 2646.21'; RECORD WPA (1930) DISTANCE AS 2643.70'
L.C.R.C. 708 L.20744 P.408 FOUND 1/2" IRON PIPE
N 80°W 38.38 NAIL IN 12" OAK (GONE)
S 64°W 23.78 NAIL IN BASE OF 7" MAPLE (GONE)
S 37°E 9.47 NAIL IN 15" MAPLE (GONE)
N 30°E 8.39 1/2" IRON PIPE (MEAS. 8.35')

(CONTINUED ON BACK)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 E 1/4 CORNER SECTION 13 T.2S., R.8E.
FOUND 3/4" IRON PIPE IN MODERATELY WOODED ACREAGE, AND IT IS ACCEPTED AS A FAITHFUL AND CAREFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
WITNESSES: N 35° E 9.24' PK NAIL NORTHWEST SIDE 16" OAK (PREVIOUSLY USED)
S 50°15' E 9.02' PK NAIL WEST SIDE TWIN 10" OAK (PREVIOUSLY USED)
S 45°10' E 20.16' NAIL/SHINER NORTH SIDE 6" OAK (W.B.C. TAG)
N 89°00' W 16.17' NAIL/SHINER SOUTH SIDE 12" OAK (W.B.C. TAG)
NORTH 8.35' 1/2" IRON PIPE (WEST 1/4 CORNER SECTION 18) (PREVIOUSLY USED)

PLACED A REMONUMENTATION BRASS TAG AND CAP #16937 ON RE-ROD.

Signed by E. Patrick O'Rourke
Surveyor's Michigan License No. 16937

Date 12-27-94

Grid table with columns A-M and rows 2-12. Includes recording stamp: \$12.00 MISCELLANEOUS RECORDING 27 DEC 94 11:03 A.M. RECEIPT# 48A RECORDED FOREST E. YOUNGBLOOD, REGISTER OF DEEDS WAYNE COUNTY, MI



LI27797PA655

SECTION A (CONTINUED)

WPA (1930) IRON SET

WITNESSES: NORTH 8.50 IRON (MEAS. 8.35')  
NE 34.05 3" CHERRY (GONE)  
SE 9.30 4" BASS (GONE)  
NW 30.84 28" MAPLE (GONE)

SECTION B (CONTINUED)

WADE-TRIM TIES 1980 (NOT RECORDED)

WITNESSES: NE 30.88 NAIL WEST SIDE 8" OAK (GONE)  
EAST 9.13 NAIL WEST SIDE 18" OAK (MEAS. 9.24)  
SE 9.05 PK NAIL WEST SIDE 10" ELM (MEAS. 9.02)  
WEST 17.14 PK NAIL SOUTH SIDE 5" OAK (GONE)

NO OTHER L.C.R.C. ON FILE AT WAYNE COUNTY REGISTER OF DEEDS.