

DEC 02 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E C-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims



Compliance with ACT 345, P.A. 1990

APPROVED ON: 11/24/93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

93 NOV 24 PM 12:08
FOREST...
REGISTERED...

P.P. Palczynski, in a field survey on 9 November, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A black dot is present at row 3, column B.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.

WITNESSES LISTED: POPLAR 9 EAST 50 (33.3') (GONE) & DO." 9 S 12.41 (8.19') (GONE)

W.P.A.- (1930'S) IRON OVER STONE. WITNESSES SHOWN: ED. POLE NE 49.13' (GONE)

12" ELM SW 33.11' (GONE)

C.S.#541, L.18421, P.24; C.S.#552, L.18421, P.40; 6" MAPLE NW 23.0' (GONE)

C.S.#554, L.18421, P.44 (5-10-73) ALL. 12" POPLAR NW 52.7' (GONE)

R.C.#706, L.20737, P.753.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD. IN MONUMENT BOX AT NEWBURGH ROAD.

MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:

C-3/C-2: W.P.A. = 2614.56' MEAS. = 2615.05'

L.C.R.C.#706 L.20737, P. 753, (12-10-79).

NAIL IN UTILITY POLE. N30°E 55.30' (MEAS. 55.30')

PIPELINE MARKER. S75°E 43.65' (MEAS. 43.55'-HIT)

N.E. COR. HOUSE #7193 S75°W 166.65' (MEAS.166.65')

IRON BAR. WEST 60.00' (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3: SECTION CORNER 5,6,7 & 8, T2S R9E, FOUND 1/2" REROD IN MONUMENT BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN N.W. FACE UTILITY POLE. N25°E 55.33'

SET NAIL/WCR TAG IN NORTH FACE UTILITY POLE. EAST 32.13'

SET CUT "X" IN NORTH RIM OF STORM MANHOLE. S35°E 53.55'

SET CUT "X" IN N.E. RIM OF CATCH BASIN. S35°W 37.68'

NORTHEAST CORNER OF HOUSE #7193. S75°W 166.65'

SET NAIL/WCR TAG IN N.E. FACE UTILITY POLE. N40°W 71.05'

Signed by [Signature]

Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

Handwritten initials: 2R 11KD