

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1458

LI27795PA293

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING
 22 DEC 94 11:59 A.M. RECEIPT# 358
 FOREST E. MANGOLD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E C-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 11-21-94 *DB-L*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, P.P. Palczynski, in a field survey on 7 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL G.L.O. SURVEYOR: FLETCHER MAY 27, 1817 **NANKIN TOWNSHIP**
 DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.
 WITNESSES LISTED: W.O. 12 S 89 W 34 (22.4') (GONE) & DO. 20 S 43 E 39 (25.7') (GONE)
 W.P.A. - (1930'S) NW-17 IRON. WITNESSES SHOWN: TEL. POLE NE 42.7' (GONE)
 POLE SE 48.53' (GONE)
 ROAD SIGN SW 42.38' (GONE)
 VENT PIPE NW 63.9' (GONE)
 R.C.#491, L. 19486, P. 378-379

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON IN MON BOX AT FORD RD / NEWBURGH RD. (ASPHALT PAVEMENT)
 MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:
 C-5/C-4: WPA=2619.31'; MEAS=2619.30'; C-5/B-5: WPA=2609.88'; MEAS=2610.18'
 B-5/C-5/C-4: WPA=90°11'50"; MEAS=90°11'38"; C-5/D-5: WPA=2630.49; MEAS=2630.40'
 C-4/C-5/D-5: WPA=89°43'45"; MEAS=89°43'03"
 R.C.#491 L19486, P378-379 (8-13-76) WCRC SEC COR WITNESS RECORD (2-13-70)
 5/8" IRON PIPE IN HAND HOLE. IRON IN BOX
 NAIL NW SIDE L.P. N45°E 72.95' (GONE) ED POLE NE 72.97' (GONE)
 NAIL SW SIDE L.P. S45°E 63.67' (GONE) ED POLE SE 63.69' (GONE)
 NAIL NW SIDE L.P. S25°W 50.21' (GONE) MBT POLE SW 50.20' (GONE)
 PK NAIL E SIDE L.P. N45°W 49.18' (GONE) BLOCK BLDG NW 62.75' (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5: SECTION CORNER 7, 8, 17 & 18, T2S R9E, FD 3/4" IRON/MON BOX IN NEWBURGH/FORD. THE
 SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY
 PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE
 ORIGINAL CORNER. PLACED W.C. REMON. BRASS MARKER AND CAP "PPP PS 30096".
 SET NAIL/WCR TAG IN SOUTHEAST FACE UTILITY POLE N35°E 86.33'
 CENTERLINE WCRC BENCHMARK BRASS DISC#70-80. N45°E 80.56'
 FOUND "X" IN NORTHWEST BOLT TRAFFIC CONTROL POLE. S45°E 82.35'
 SET NAIL/WCR TAG IN NORTHWEST FACE UTILITY POLE. S20°W 84.29'
 CENTERLINE OF FIRE HYDRANT STEM. S50°W 78.68'
 SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE. N35°W 77.72'

Signed by *P.P. Palczynski* Date 22 DEC 94

Surveyor's Michigan License No. 30096

RC 1458

2R
110-MISC