

SURVEY & REMONUMENTATION

RC 1459

L127795PA294

APR 25 1995

\$ 13.00 MISCELLANEOUS RECORDING
22 DEC 94 12:01 P.M. RECEIPT# 358

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
FOR THE REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E C-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-21-94 *DPF*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, P.P. Palczynski, in a field survey on 7 November, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL G.L.O. SURVEYOR: FLETCHER MAY 27, 1817.
DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.
WITNESSES LISTED: BEECH 10 S77W 16 (10.6') (GONE) & SUG 16 S61E 52(34.3') (GONE)
W.P.A.-(1930'S) NW-32 IRON. WITNESSES SHOWN: STONE N 0.30' (GONE)
8" ELM SE 29.75' (GONE) ED POLE SE 41.43' (GONE)
36" OAK SW 36.00' (GONE) 16"WALNUT NW 50.30' (GONE)

NANKIN TOWNSHIP

RC 1459

C.S.#65 L.17952, P.195(12-14-71) & R.C.#676, L.20536, P.283(4-20-79).
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" STEEL BAR IN MONUMENT BOX AT NEWBURGH ROAD. (CONC. PVT.)
MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:
C-11/C-10 W.P.A. = 2617.73' MEAS. = 2619.41'.
C.S.#65 L.17952, P. 195 MONUMENT NOT STATED.
P.K. NAIL IN SW SIDE OF WOOD POLE N54°E 71.85' (GONE)
TOP OF CONC. BASE FOR LIGHT POLE S79°E 74.00' (GONE)
P.K. NAIL IN NW SIDE OF WOOD POLE S17°30'E 128.00' (MEAS=128.05')
R.C.#676 L.20536, P.283, 1/2" IRON IN MONUMENT BOX.
6" ELM S30°E 51.00' (GONE) NE BOLT LITE STD S56°E 74.99' (MEAS=74.99')
6" ASH N55°W 51.58' (MEAS = 51.31')
TEL POLE N50°E 72.34' (MEAS = 72.25')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-11:SECTION CORNER 29,30,31,&32 T2S R9E, FOUND 1/2" STEEL BAR IN MON. BOX. THE
SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY
PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE
ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".
SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE. N55°E 72.25'
FOUND P.K. NAIL IN EDGE OF ASPHALT PARKING LOT. EAST 59.85'
SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE. S25°E 128.46'
SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE. S20°W 156.43'
SET NAIL/WCR TAG IN NORTHEAST FACE OF 12" ASH. N48°W 47.99'
FOUND NAIL/MDSH TAG IN SOUTHWEST FACE 12" ASH. N45°W 51.31'

*2 R
11 D. Misc*

Signed by *PP* Date 22 DEC 94

Surveyor's Michigan License No. 30096