

**SURVEY & REMONUMENTATION**

**RC 1460**

**L127795PA295**

\$ 13.00 MISCELLANEOUS RECORDING  
22 DEC 94 12:01 P.M. RECEIPT# 35B

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**COMMISSION**

For corners in

**WAYNE**

(County)

Located In:

Corner Code =#

- 1. Public Land Survey T 2S R 9E C-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_



Compliance with  
**ACT 345, P.A. 1990**  
APPROVED ON: 11-21-94 *POA.*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, P.P. Palczynski, in a field survey on 7 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
ORIGINAL G.L.O. SURVEYOR: FLETCHER MAY 27, 1817. **NANKIN TOWNSHIP**  
DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.  
WITNESSES LISTED: W.O. 20 N51E 23 (15.2') (GONE) & B.O. 24 S84E 98 (64.7') (GONE)  
GLO NOTES-T3S, R9E: "FELL 1.79 (118.14') W OF POST COR 31, 32 T2S, R9E"  
W.P.A.-(1930'S) SW-32 IRON. WITNESSES SHOWN: ED POLE NE 63.74' (GONE)  
15" MAPLE SE 83.62' (GONE) 15" MAPLE SE 69.17' (GONE)  
ROOT 30" MAPLE S 25.47' (GONE) IRON W 115.64' (MEAS=115.87')  
C.S.#1120 L.19125, P.305-306 (5-17-75)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" STEEL BAR IN CONC MON/MON BOX IN VAN BORN ROAD. (ASPHALT PVT.)  
MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:  
C-13/D-13 W.P.A. = 2611.69' MEAS. = 2611.54'.  
C-13/B-13 W.P.A. = 2631.32' MEAS. = 2631.79'  
B-13/C-13/D-13 W.P.A. = 180° 01' 15" MEAS. = 180° 02' 10"  
C.S.# 1120, L19125, P305-306 (5-17-75)  
NAIL WITH SQUARE TAB IN D.E. POLE NE 56.11' (MEAS=56.02')  
NAIL WITH SQUARE TAB IN MBT. POLE SE 57.85' (GONE)  
MONUMENT IN ROAD BOX WEST 115.82' (MEAS=115.87')
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-13: SECTION CORNER 31&32 T2S R9E, FOUND 1/2" IRON BAR IN CONC MON/MON BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".  
SET NAIL/WCR TAG IN SOUTHEAST FACE OF 15" BEECH. N36°E 58.88'  
SET NAIL/WCR TAG IN SOUTHEAST FACE OF UTILITY POLE. N54°E 56.31'  
SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE. S54°E 56.22'  
SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE. S68°W 87.47'  
FOUND 1/2" STEEL BAR IN BROKEN MON/MON BOX. WEST 115.87'  
SET NAIL/WCR TAG IN SOUTH FACE OF UTILITY POLE. N70°W 99.37'

**RC 1460**

*2R  
H.D. MISC*

Signed by *[Signature]* Date 22 DEC 94

Surveyor's Michigan License No. 30096