

L129358PA638

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County) Located In: Corner Code #/
1. Public Land Survey T 2 S R 9 E D-13
CITY OF WAYNE
NANKIN TOWNSHIP
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: DEC 18, 1996
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Grid table with columns A-K and rows 2-13. Cell 10,3 contains a black dot.

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST MAPLE 9" N56°E 20 LKS.
JOSEPH FLETCHER Do. S2°E 29 LKS.

26 DEC 96 8:21 A.M. RECEIPT# 18
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
\$ 4.00 REMONUMENTATION

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" STEEL BAR IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF VAN BORN ROAD ASPHALT PAVEMENT, 45.79' EAST OF EAST EDGE OF R.R. RAIL.
MEASURED: C-13/D-13/E-13 = 179°52'18" E-13/D-13/C-13 = 180°07'42"
D-13 IN T2S, R9E, IS NOT THE SAME CORNER AS D-1, T3S, R9E.

CORNER POSITION VERIFIED USING 1 WITNESS AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED: D-13 / E-13 = 2635.22' (R=2634.13') D-13 / C-13 = 2611.54' (R=2611.69')



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, T2S, R9E
FOUND 1/2" STEEL BAR IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF VAN BORN ROAD ASPHALT PAVEMENT, 45.79' EAST OF EAST EDGE OF R.R. RAIL, SET WAYNE COUNTY REMON. BRASS MARKER AND CAP "PPP PS 30096" ON BAR.
SET NAIL/WCR TAG IN WEST FACE OF UTILITY POLE N11°E 53.26'
FOUND P.K. NAIL IN EAST FACE OF UTILITY POLE N15°E 37.75'
SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE N68°E 137.55'
SET NAIL/WCR TAG IN NORTH FACE OF UTILITY POLE S78°E 152.93'
FOUND CUT "X" IN EAST FACE OF CONCRETE FIBER OPTICS MARKER S25°W 91.05'
EAST EDGE OF RAILROAD RAIL (5) (R=46.65') WEST 45.79'
FOUND P.K. NAIL IN SOUTHWEST FACE OF UTILITY POLE N72°W 105.29'
SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE N63°W 114.23'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 23 DEC 96

Surveyor's Michigan License No. 30096
2S9ED-13.DOC

**1996 WAYNE COUNTY REMONUMENTATION PROGRAM**

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
D-13 (SOUTH 1/4 CORNER SECTION 32)

*History compiled by:*  
Peter P. Palczynski, P.S. # 30096  
AMBIT LAND SURVEYORS, INC.

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST FOR D-13 T2S., R.9E., NANKIN.	MAPLE 9" Dp.	N56°E 20 LKS. S02°E 29 LKS.		NOTES = 40.00 CHAINS
1990S	W.P.A.				CROSS (S-32 #166 FOR NANKIN TOWNSHIP T2S., R9E)	ED POLE 16" MAPLE ED POLE IRON SET FOR D-1, T3S, R9E GAUGE OF EAST RAIL MAIN TRACK	NE 34.65' NE 63.03' SE 31.25' WEST 55'+/- WEST 46.65'	1 2 3 4 5	GONE GONE GONE GONE M = 45.79' EAST EDGE

**W.P.A. RECORD:**

- D-13 / E-13 = 2634.13'
- D-13 / C-13 = 2611.69'
- C-13 / D-13 / E-13 = 179°54'30"
- E-13 / D-13 / C-13 = 180°05'30"

LI29358 PA639