

SURVEY & REMONUMENTATION

DEC 02 1993

COMMISSION

RC 1136

LI 26985 PA 927

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **WAYNE**
 (County)

Located In: Corner Code **#**

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2S</u> R <u>9E</u> | <u>G-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Compliance with **ACT 345, P.A. 1990**

APPROVED ON: 11/24/93 NCD
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

96 NOV 24 PM 12:08 RC 1136
 FOREST COUNTY REGISTER OF DEEDS
 1000 1ST AVENUE
 SPOKANE, IDAHO 83402

I, **P.P. Palczynski**, in a field survey on **10 November**, 19**93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.

WITNESSES LISTED: B.ASH 12 N21E 9 (6.0') (GONE) & W.ASH 30 N81E 28 (18.5') (GONE)

W.P.A.- (1930'S) CROSS ON STONE. WITNESSES SHOWN:

N. END OF E. RAIL ON BRIDGE	SE	55.10' (GONE)
TWIN WALNUT	SW	46.00' (MEAS. 44.92')
16"WALNUT	WEST	34.00' (MEAS. 32.97')

C.S. #1939 L.23982 P.825 (10-26-88). NO SUBSEQUENT L.C.R.C. FORMS ON RECORD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN STEEL ENCASED CONCRETE MONUMENT (0.8' DEEP) IN HINES PARK.

MEASURED DISTANCE FOR COMPARISON TO W.P.A. RECORDS:

G-2/G-3:	W.P.A. = 2656.24'	MEAS. = 2655.91'
C.S. #1939 :	= 2655.75'	(10-26-88)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2:SECTION CORNER 3&4, T2S R9E, FOUND 3/4" IRON PIPE IN STEEL ENCASED MON. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN NW FACE 24" TWIN WALNUT.	N55°E	22.09'
SET NAIL/WCR TAG IN NE FACE UTILITY POLE.	S30°E	43.75'
SET NAIL/WCR TAG IN SE FACE 30" WALNUT.	S35°W	44.92'
FOUND 3/4" IRON PIPE IN STEEL ENCASED CONCRETE MONUMENT.	WEST	37.95'
SET NAIL/WCR TAG IN NORTH FACE 24" WALNUT.	WEST	32.97'

Signed by *PP* Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

*26
11K*